

Document Number:
400294345

Date Received:
06/11/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type Final completion Preliminary completion

1. OGCC Operator Number: 47120 4. Contact Name: JOEL MALEFYT
 2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6828
 3. Address: P O BOX 173779 Fax: (720) 929-7828
 City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33729-00 6. County: WELD
 7. Well Name: HOWARD Well Number: 28-32
 8. Location: QtrQtr: SWNE Section: 32 Township: 1N Range: 67W Meridian: 6
 Footage at surface: Distance: 2411 feet Direction: FNL Distance: 1544 feet Direction: FEL
 As Drilled Latitude: 40.008226 As Drilled Longitude: -104.910379

GPS Data:
 Date of Measurement: 11/14/2011 PDOP Reading: 1.7 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 53 feet. Direction: FNL Dist.: 2582 feet. Direction: FWL
 Sec: 32 Twp: 1N Rng: 67W
 ** If directional footage at Bottom Hole Dist.: 47 feet. Direction: FNL Dist.: 2592 feet. Direction: FWL
 Sec: 32 Twp: 1N Rng: 67W

9. Field Name: SPINDLE 10. Field Number: 77900
 11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 10/29/2011 13. Date TD: 10/31/2011 14. Date Casing Set or D&A: 11/01/2011

15. Well Classification:
 Dry Oil Gas/Coalbed Disposal Stratigraphic Enhanced Recovery Storage Observation

16. Total Depth MD 8965 TVD** 8418 17 Plug Back Total Depth MD 8937 TVD** 8390

18. Elevations GR 5061 KB 5076
 One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:
CBL; NO OPEN HOLE LOGS RUN

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24	0	1,213	760	15	1,213	CALC
1ST	7+7/8	4+1/2	11.6	0	8,954	64	8,640	8,604	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 11/01/2011

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	8,624	1,051	500	8,624

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,178		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,751		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,966		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	8,384		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,809		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JOEL MALEFYT
 Title: REGULATORY ANALYST Date: 6/11/2012 Email: JOEL.MALEFYT@ANADARKO.COM

Attachment Check List

Att Doc Num	Document Name	attached ?	
<u>Attachment Checklist</u>			
400294364	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400294373	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<u>Other Attachments</u>			
400294345	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
400294397	DIRECTIONAL DATA	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	Corrected field name from Wattenberg to Spindle.	9/21/2012 8:22:00 AM

Total: 1 comment(s)