

P&A Procedure for the SGU CP07C-27 L27 496

Garfield Co., Colo.

9 5/8" 36# at 2,430' TOC at Surface

7" @ 8,308' TOC at 7,000', P&A to 37'

Tubing: none

Perfs: none

PBTD: 37'

Well is plugged to 37'

Confirm cement to 37' (tag with hand held line)

If not call for orders.

Fill casing with cement from 37' to surface.

Cut off wellhead

Weld a plate with well information

Marker jts: Tops @ 492' (37.49')
 @ 1207' (38.74')
 @ 2343' (37.60')
 @ 2550' (39.13')
 @ 2801' (38.08')
 @ 2967' (38.04')
 @ 3302' (38.00')
 @ 4141' (38.01')
 @ 4179' (39.20')
 @ 5151' (39.31')