



TICKET NUMBER 33693  
LOCATION Oakley  
FOREMAN Kelly Gabel

**PO Box 884, Chanute, KS 66720**  
**620-431-9210 or 800-467-8676**

## FIELD TICKET & TREATMENT REPORT CEMENT

colo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
11-10-11	9160	Napali #4	17	10	55 <sup>W</sup>	Lincoln	
CUSTOMER Wheipking Fullerton			Limon COLO 45 2 W Emito	TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS				463	Josh G		
				439	Wes F		
CITY		STATE	ZIP CODE				

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>325</u>	CASING SIZE & WEIGHT <u>8 5/8 24#</u>
CASING DEPTH <u>307</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>30'</u>
DISPLACEMENT <u>17 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety meeting, rigged up on martin drilling Rig #25.  
Hooked up to circulate. Mixed 265 5x5 Com 3% cc & 2% gel.  
Released plug. Displaced with 17 1/2 bbl H2O. Shut in & washed  
out pumps & lines. Rigged down & left location.

Cement did circulate & circulated approx. 3 bbl cement top ft.

Thanks  
Kelly & crew

[illegible]

Rayin 3737

12:00 PM

## AUTHORIZTION

**TITLE**

TITLE Co-Rep

DATE 11/01/1

DATE 11/10/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676



# FIELD TICKET & TREATMENT REPORT

## CEMENT

TICKET NUMBER 33750  
LOCATION Oakley Ks  
FOREMAN Walt Dunkel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-24-11	9160	Napali #4	19	10S	55W	Lincoln
CUSTOMER <u>Weirking-Fullerton Energy</u>			Limon Colo 55			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
			399 #	Damon Miller		
			566 #	Wes F		
				Miles Shaw		
CITY	STATE	ZIP CODE				

JOB TYPE Prod-O HOLE SIZE 7 7/8 HOLE DEPTH 7870' CASING SIZE & WEIGHT 5 1/2 - 17#  
CASING DEPTH 7856' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT 14# SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 40.30  
DISPLACEMENT 18374 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 6-7 BPM

REMARKS: Safety Meeting, Rig up on MurFin #25, run Float Equipment  
Turbo-Cent 4, 3, 5, 7, 9, 11, 13, 15, 17, 20, 21, 22, Port Collar on 81, Basket on 81  
Cent 80-82, run 100 Jts, circ 1 1/2 hrs, run to Bottom, circ Hrs  
Pump 500 gal Mud Flush, mix 5 SKs in Rth, 5 SKs in Mth, 1/4# Flo-Seal  
mix 250 SKs class H, 10% salt, 5# Kolseal, 2% Gel, Clear Pump + Lines  
release Plug + Displace 183-BBL H2O @ 1200# #, Landed Plug @ 1600#  
release Pressure, Float Held

Thank You  
Walt + Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	40.50 <sup>00</sup>	40.50 <sup>00</sup>
5406	100	MILEAGE	5.00	500.00
1115 A	2.60 SKs	Class H Cement	22.00	57.20 <sup>00</sup>
1111	1243 #	Salt	1.42	522.06
1110 A	1300 #	Kolseal	1.53	689.00
1118 B	488 #	Bentonite Gel	1.24	117.12
1107	65 #	Flo-Seal	2.66	172.90
1144 B	500 gal	Mud Flush	1.00	500.00
5407A	12.22	Ton Mileage Delivery	1.58	19.31 <sup>00</sup>
4159	1	AFU Float Shoe	413.00	413.00
4454	1	Latch down Plug Assembly	303.00	303.00
4136	12	Turbo-Centralizers	72.00	864.00
4130	2	Centralizers	58.00	116.00
4104	2	Baskets	276.00	552.00
4285	1	Port Collar	2075.00	2075.00
				18,525.00
		Less 10% Disc		18,525.00
				16,672.57
		246095	SALES TAX	845.50
			ESTIMATED TOTAL	17518.07

Ravin 3737

AUTHORIZATION Benny Smith TITLE Co rep DATE 11/24/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



AUTHORIZATION [Signature] TITLE [Signature]  
I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.