

FORM  
5A

Rev  
06/12

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400336395

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322  
2. Name of Operator: NOBLE ENERGY INC  
3. Address: 1625 BROADWAY STE 2200  
City: DENVER State: CO Zip: 80202  
4. Contact Name: Eileen Roberts  
Phone: (303) 2284330  
Fax: (303) 2284286

5. API Number 05-123-34611-00  
6. County: WELD  
7. Well Name: MANSFIELD E  
Well Number: 36-65HN  
8. Location: QtrQtr: SWNW Section: 36 Township: 6N Range: 65W Meridian: 6  
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 03/14/2012 End Date: 03/14/2012 Date of First Production this formation: 03/26/2012

Perforations Top: 7273 Bottom: 11054 No. Holes: 0 Hole size: 0

Provide a brief summary of the formation treatment: Open Hole: ☐

Frac'd the Niobrara w/ 2852030 gals of Silverstim and Slick water with 3,920,463#s of Ottawa sand.

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 72747 Max pressure during treatment (psi): 6647

Total gas used in treatment (mcf): 0 Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 1.02

Total acid used in treatment (bbl): 0 Number of staged intervals: 17

Recycled water used in treatment (bbl): Flowback volume recovered (bbl):

Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE

Total proppant used (lbs): 3955081 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 03/30/2012 Hours: 24 Bbl oil: 571 Mcf Gas: 1110 Bbl H2O: 240

Calculated 24 hour rate: Bbl oil: 571 Mcf Gas: 1110 Bbl H2O: 240 GOR: 1943

Test Method: FLOWING Casing PSI: 2400 Tubing PSI: 1900 Choke Size: 016/64

Gas Disposition: SOLD Gas Type: WET Btu Gas: 1256 API Gravity Oil: 52

Tubing Size: 2 + 7/8 Tubing Setting Depth: 7004 Tbg setting date: 03/25/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Eileen Roberts \_\_\_\_\_

Title: Regulatory Specialist Date: \_\_\_\_\_ Email: eroberts@nobleenergyinc.com  
:

### **Attachment Check List**

Att Doc Num	Name

Total Attach: 0 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>

Total: 0 comment(s)