

WPX Energy Rocky Mountain, LLC

Federal RG 11-23-298

Sulphur Creek Field

SHL 261' FSL 1976' FWL (SE/4 SW/4) BHL 224' FNL 675' FWL (NW/4 NW/4 Sec. 23, T2S, R98W)

Section 14-T2S-R98W 6th PM

Garfield County, Colorado

Formation Tops

(Measured Depths)

Mesaverde @ 6341'

Cameo @ 9216'

Rollins @ 9786'

Cozzette @ 9916'

Corcoran @ 10139'

Sego @ 10483'

PBTD @ 10825'

TMD @ 10939'

TVD @ 10747'

Conductor 30" Hole 18" casing/liner 80' W/135 sks cmt

Cmt @ Surface - (Cmt circ to surf during cmt job)

9 5/8" 36# ppf Csg. Set @ 3454'

In 14 3/4" Hole W/1555 Sks. Cmt

Top Of Cement 4588'

8304-8508'	Mesaverde
8564-8787'	Mesaverde
9054-9241'	Mesaverde
9315-9468'	Cameo
9556-9719'	Cameo
10167-10406'	Corcoran
10490-10608'	Sego
10625-10789'	Sego

4-1/2", 11.6 ppf. Csg. Set @ 10929' W/ 1590 sks Cmt