



State
of
Colorado

Coler, Larry <larry.coler@state.co.us>

Fwd: Sidetrack, CHANDLER CREEK 24-32, 05-043-06196

2 messages

Sutphin, Dirk <dirk.sutphin@state.co.us>
To: Larry Coler <larry.coler@state.co.us>

Thu, Oct 11, 2012 at 2:39 PM

Larry,
Sorry I missed you earlier.

//Dirk

----- Forwarded message -----

From: **Sutphin, Dirk** <dirk.sutphin@state.co.us>
Date: Thu, Oct 11, 2012 at 2:15 PM
Subject: Re: Sidetrack, CHANDLER CREEK 24-32, 05-043-06196
To: Tom Menhennett <tbm3040@gmail.com>
Cc: Diana Burn <diana.burn@state.co.us>, Mike Leonard <mike.leonard@state.co.us>, Jane Stanczyk <jane.stanczyk@state.co.us>

Tom,
Looks good. Please repeat this info on page 2 of the Form 4 and send the Form 4 and Form 2 with attachments to Larry and/or eForms, per the Sidetrack Approval Reporting document. This is your verbal notice to proceed. For convenience I am copying the text of your procedure (see below and attached). The date of the text should be 10/11/12 (today) rather than 9/10/12 as written.

Thank you,

Dirk Sutphin, P.E.
COGCC, SE Area Engineer
(303) 894-2100 x 5107

From: Javernick Oil LLC

To: COGCC

Regarding: Sidetrack of Chandler Creek 24-32

Date: 09/10/2012

- i. The need for this sidetracking was that we missed our target.
- ii. TD in existing wellbore was 3710'
- iii. Casing Size 7" Depth Set 300'
- iv. No fish in hole.
- v. Proposed Plug @ 2400' by Filling from 3710' to 2400' w 10 Sack Grout Mix, Total of 10 yards

- vi. 10 Sack Grout Mix; 2370 Lbs Sand, 752 Lbs Cement, 188 Lbs Fly-ash, 50 Gal H2O, 2 oz Air
- vii. Measured depth of sidetrack kick-off point is 2400'
- viii. Formation would be the same Pierre
- ix. BHL target is 55' FSL 2050FWL Lat 38.3451961 Long -105.1362266

On Thu, Oct 11, 2012 at 9:19 AM, Tom Menhennett <tbm3040@gmail.com> wrote:

-

Tom Menhennett- CFO Javernick Oil LLC
3040 E. Main St- Canon City, CO 81212
Phone: 719-275-3040
Fax: 719-275-4590