



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**601005**

Date	9/12/2012	Well Owner	Kerr McGee	Well No.	12-1	Lease	PEHR
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME#11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	939		
Surface	8 5/8" CSG 24"	Bottom of Surface		FL	929		
Plug		Plug Landed @	984	FL	Time On	1930	
Production		Pipe Landed @	928	FL	Plug Down	2200	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	580	SKS		
Poz. Mix ED ASUCHAK				
Calcium Chloride T2K 418	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack 2.053379 0126				
Mileage Charge 800/2090	210	Miles		
Fuel Surcharge	210	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	2109	2114		
Disp. Rate 5 BPM	2114	2146		
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	2146	2149		
Slurry Wt. 14.8 - 15.0 PPG	2149	2200		
Water/Cement 6.25 Gal/SK				
Water Temp. 61				
Total Slurry Vol. 126.3		BBLS Cement		
Landed Plug @ 400		PSI/Final Lift @ 125	PSI	
Pre-Flush W/ 30		BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/ 56.2		BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate 6		BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		70			
1216/1219		Bulk Truck		70/70			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Joshua / JSH2

Received By D. S. H.  
Customer or His Agent