

Magna Energy Services, LLC
17509 County Road 14,
Ft. Morgan, Colorado 80701
(970)-867-9007 or (970)-867-8374 (Fax)
Job Log

Date: 10-5-12

Operator: EnCana Oil and Gas
Well name: North Parachute WF 02B-A15 596
Location: Garfield County, Colorado
Legals: NENW, Section 15, 5 South, 96 West
AFE #:

MIRU, TIH with tubing and hard tag at 2,407', TOH to 2,402'
Pump 40 sxs of cement into 9-5/8" casing, Displaced with 9 bbl. of water, TOH and WOC
TIH and tagged TOC at 2,285', TOH to 110', Pump 44 sxs of cement to surface
TOH, Dug out casing, Cut 16" and 9-5/8" casing four feet below ground level
Welded information plate onto 16", backfilled pit
RDMO

*** All cement is 15.8# Class "G" neat cement, yield 1.15 ***

Cementing contractor: Magna Energy Services, LLC
Cementing contractor supervisor: Jeremy Rose
Operator supervisor: Steve Vencill
COGCC Representative: Mike Longworth
Wireline contractor: None