



State
of
Colorado

Krabacher, Jay <jay.krabacher@state.co.us>



CBL Deferment for Shideler Fee 31-5BB

2 messages

Reynolds, Scott D. <Scott.Reynolds@encana.com>


Sun, Oct 14, 2012 at 10:29 PM

To: "Krabacher, Jay (Jay.Krabacher@state.co.us)" <Jay.Krabacher@state.co.us>, "King, Kevin" <Kevin.King@state.co.us>

Kevin, Jay,

This was actually due to you on Friday the 12th but I came down with a bug and spent the day at home and completely forgot about it until this evening.

EnCana CBL Deferment Request



Well Name:	Shideler Fee 31-5BB
API Number:	05-045-21623-00
Pad Name:	K31E
Casing Size	4-1/2" 11.6# S80 BTC
Casing Setting Depth	9,600' MD-RKB
Plug Bump Date:	10-09-2012
Plug Bump Time:	17:00 hours
Top of MV:	4966' MD-RKB
Top of Gas:	6509' MD-RKB
Designed TOC:	4266' MD-RKB
Temp Log TOC:	4500' MD-RKB

Bradenhead Pressure Report

Time	Bradenhead Pressure
6 hours	0
12 hours	0

24 hours	0
48 hours	0
72 hours	0

Comments:

Cement As Follow's: 40bbls. Mud Push II,11#, Lead 160bbls,12#TXI,501sks,Yeild 1.79,Water/sk. 10.04, Tail 183bbls., 13#TXI,546sks.,Yeild 1.88,Water/sk. 9.48, Drop Plug & Displace W/ 148.5 bbls. Water. Circ. Press. 1,500psi, Bump Plug W/ 1K over Circ. Press. 2,500psi, Hold Pressure For 10Min. No Leak off, Bleed Press. off Floats Held., 1bbl. Water Back. Hole Static..

Scott Reynolds**Drilling Engineer – South Piceance****Encana Oil & Gas (USA) Inc****O: 720.876.5255****C: 303.895.0445****F: 720.876.6255****scott.reynolds@encana.com****Take a closer look: www.encana.com****Please note: Encana offices are closed the first and third Friday of each month**

This email communication and any files transmitted with it may contain confidential and or proprietary information and is provided for the use of the intended recipient only. Any review, retransmission or dissemination of this information by anyone other than the intended recipient is prohibited. If you

receive this email in error, please contact the sender and delete this communication and any copies immediately. Thank you.

<http://www.encana.com>

 **CADB-00028_ENCANA_SHIDELER_FEE_31_5BB_TEMP_LOG_Combined.PDF**
641K

Krabacher, Jay <jay.krabacher@state.co.us>
To: "Reynolds, Scott D." <Scott.Reynolds@encana.com>
Cc: "King, Kevin" <Kevin.King@state.co.us>

Thu, Oct 18, 2012 at 9:09 AM

Scott:

Encana can defer the CBL on the subject well.

Regards,

Jay Krabacher
[Quoted text hidden]