



Daily Report for Rig # 8 (2)

Jeremy Rose <jrose@magnaes.com>

Sun, Oct 21, 2012 at 5:56 PM

To: "Dave Rebol (daverebol@hotmail.com)" <daverebol@hotmail.com>, "harlanhodge@hotmail.com" <harlanhodge@hotmail.com>, "john.miller3@EnCana.com" <john.miller3@encana.com>, "Kathy highberger (dkama@kci.net)" <dkama@kci.net>, Ryan Ludwar <rludwar@magnaes.com>
Cc: "aronrt@hotmail.com" <aronrt@hotmail.com>, "nortonjr69@gmail.com" <nortonjr69@gmail.com>, "david.andrews@state.co.us" <david.andrews@state.co.us>, "mike.longworth@state.co.us" <mike.longworth@state.co.us>

DATE: 10/21/2012

OPERATOR: EnCana Oil and Gas

WELL NAME: NPM CP12D – 16 E16 596

COUNTY: Garfield, Colorado

API #: 05045135370000

1:00-1:30 Cut and remove 9-5/8" casing and well head.

1:30-2:30 Trip in hole with 1" tubing to 105' of 9-5/8" casing and pump 46 sacks of cement to surface.

2:30-3:30 Weld info cap onto 9-5/8" casing. Back fill pit around casing.

All cement pumped was 15.8# Class "G" Neat with a yield of 1.15