

**State of Colorado**  
**Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400336964

Date Received:

PluggingBond SuretyID

20110188

**APPLICATION FOR PERMIT TO:**

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

## 2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_

SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling 

Sidetrack 

3. Name of Operator: TEKTON WINDSOR LLC 4. COGCC Operator Number: 10392

5. Address: 640 PLAZA DRIVE #290

City: HIGHLANDS State: CO Zip: 80129  
RANCH

6. Contact Name: CLAYTON DOKE Phone: (970)669-7411 Fax: (970)669-4077

Email: cdoke@petersonenergy.com

7. Well Name: RANCHO WATER VALLEY 13 Well Number: 7-6-33-270-6-CH

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 14185

## WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 4 Twp: 5N Rng: 67W Meridian: 6

Latitude: 40.435480 Longitude: -104.888570

			FNL/FSL			FEL/FWL
Footage at Surface:	220	feet	FNL	398	feet	FEL

11. Field Name: WATTENBERG                      Field Number: 90750

12. Ground Elevation: 4775 13. County: WELD

- #### 14. GPS Data:

Date of Measurement: 09/26/2012 PDOP Reading: 1.8 Instrument Operator's Name: WYATT HALL

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone:				FNL/FSL	FEL/FWL	Bottom Hole:				FNL/FSL	FEL/FWL				
<u>1320</u>		<u>FSL</u>		<u>460</u>		<u>FEL</u>		<u>1320</u>		<u>FSL</u>		<u>2054</u>		<u>FEL</u>	
Sec:	33	Twp:	6N	Rng:	67W	Sec:	32	Twp:	6N	Rng:	67W				

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 231 ft

18. Distance to nearest property line: 220 ft      19. Distance to nearest well permitted/completed in the same formation(BHL): 660 ft

20. **LEASE, SPACING AND POOLING INFORMATION**

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL			GWA

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #:

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

- 23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

- 23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

TOWNSHIP 6 NORTH, RANGE 67 WEST, SECTION 33; ALL EXC SW/4, SECTION 32; ALL EXC SW/4

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 960

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,220	640	1,220	0
1ST	8+3/4	7	23	0	7,472	125	7,472	6,488
1ST LINER	6+1/8	4+1/2	11.6	6703	14,185			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments No conductor casing will be run. Pad slot #13. This well is a Rule 318A(I).a.(4)D Horizontal GWA Well; Proposed Spacing Unit: SE/4 SEC. 32 & S/2 SEC. 33 T6N-R67W. PSU Map is attached. Well distance to nearest spacing unit boundary = 460'. 318A(I).a.(4) well, notices were mailed: 10/24/12. The affidavit of mailing is attached. 30-day certification detailing if objections were received will be sent on or about 11/23/12 contingent upon the date of receipt and after the 30-day period has expired. This well is being permitted under the provisions of Rule 318A(I).c.(3); an existing location exception waiver is already on file with the state [Doc#: 400227152] along with an associated request [Doc#: 40027176] for this location, thus no additional waiver or request has been attached. SUA is attached.

34. Location ID: 427157

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: CLAYTON DOKE

Title: PETROLEUM ENGINEER Date: \_\_\_\_\_ Email: cdoke@petersonenergy.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

### Attachment Check List

Att Doc Num	Name
400338435	WELL LOCATION PLAT
400338437	DEVIATED DRILLING PLAN
400338441	DIRECTIONAL DATA
400338443	PROPOSED SPACING UNIT
400339342	PROPOSED SPACING UNIT
400339345	SURFACE AGRMT/SURETY

Total Attach: 6 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Drilling/Completion Operations	Bradenhead Monitoring BMP: Operator will comply with COGCC Policy for Bradenhead Monitoring During Hydraulic Fracturing Treatments in the Greater Wattenberg Area dated May 29, 2012.
Drilling/Completion Operations	Anti-Collision BMP: Prior to drilling operations, Operator will perform an anti-collision scan of existing offset wells that have the potential of being within close proximity of the proposed wells. This anti-collision scan will include definitive MWD or gyro surveys of the offset wells with included error of uncertainty per survey instrument, and compared against the proposed wellpath with its respective error of uncertainty. If current surveys do not exist for the offset wells, Operator may have gyro surveys conducted to verify bottomhole location. The proposed well will only be drilled if the anti-collision scan results indicate that there is not a risk for collision, or harm to people or the environment. For the proposed well, upon conclusion of drilling operations, an as-constructed gyro survey will be submitted to COGCC with the Form 5.

Total: 2 comment(s)