

FORM  
2

Rev  
12/05

# State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400339743

Date Received:

## APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20100108

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 500 DALLAS STREET #2300

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Tina Taylor Phone: (713)328-1000 Fax: (713)328-1060

Email: tina.taylor@crzo.net

7. Well Name: Bringelson Well Number: 1-32-9-58

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 10169

## WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 32 Twp: 9N Rng: 58W Meridian: 6

Latitude: 40.700830 Longitude: -103.883020

Footage at Surface: 250 feet FNL/FSL FSL 1325 feet FEL/FWL FEL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4785 13. County: WELD

### 14. GPS Data:

Date of Measurement: 08/29/2012 PDOP Reading: 1.8 Instrument Operator's Name: Marc Woodard

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 650 FSL 1900 FEL FEL Bottom Hole: FNL/FSL 650 FNL 1900 FEL FEL  
Sec: 32 Twp: 9N Rng: 58W Sec: 32 Twp: 9N Rng: 58W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 250 ft

18. Distance to nearest property line: 250 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1250 ft

## 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		640	SE/4

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
 Township 9 North Range 58 West 6th P.M.: SE/4 of Section 32; NE/4, W/2, N2SE/4 Section 33; N/2 Section 34:T9N R58W, 6th P.M.,  
 25. Distance to Nearest Mineral Lease Line: 235 ft 26. Total Acres in Lease: 1040

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.  
 28. Will salt sections be encountered during drilling?  Yes  No  
 29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No  
 30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No  
 31. Mud disposal:  Offsite  Onsite **If 28, 29, or 30 are "Yes" a pit permit may be required.**  
 Method:  Land Farming  Land Spreading  Disposal Facility Other: \_\_\_\_\_  
 Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
1ST	8+3/4	7	23	0	5,972	550	5,972	1,400
1ST LINER	6+1/4	4+1/2	11.6	5256	10,169			

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None  
 33. Comments Application for a drilling and spacing unit has been made and is on the Nov 15, 2012 docket for approval. No conductor casing will be set. Swell Packer will be set across 600' from section line to keep wellbore from 7" casing shoe to Swell Packer unproduced.

34. Location ID: 424273  
 35. Is this application in a Comprehensive Drilling Plan ?  Yes  No  
 36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No  
 I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.  
 Signed: \_\_\_\_\_ Print Name: Tina Taylor  
 Title: Regulatory Compliance Date: \_\_\_\_\_ Email: tina.taylor@crzo.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**API NUMBER** Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

**05**

**CONDITIONS OF APPROVAL, IF ANY:** \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

\_\_\_\_\_

### Attachment Check List

Att Doc Num	Name
400339767	WELL LOCATION PLAT
400339768	DEVIATED DRILLING PLAN
400339793	DIRECTIONAL DATA

Total Attach: 3 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.
Storm Water/Erosion Control	Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.
Construction	The location will be fenced
Site Specific	Operator will participate in the Colorado Oil & Gas Association Voluntary Baseline Groundwater Quality Sampling Program. Operator will implement interim reclamation measures immediately after construction of the location to stabilize cut and fill slopes, stabilize the topsoil and spoil stockpiles, establish desirable vegetation and control weeds on the location.

Total: 4 comment(s)