



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600537

Date	7/9/12	Well Owner	Kerr McGee	Well No.	13N-10H2	Lease	CANON
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (major #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Ft. 810			
Surface	9 5/8" C.S.G. 36" 13 1/2" Hole		Bottom of Surface	Ft. 804			
Plug			Plug Landed @	763	Ft.	Time On 1100	
Production			Pipe Landed @	804	Ft.	Plug Down 1330	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack 17-1/2				
Mileage Charge 2073/49	126	Miles		
Fuel Surcharge 800/2090	126	miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	1234	1240		
Disp. Rate 5 BPM	1240	1315		
Slurry Vol. 1.32° Cu.Ft./Sk	1315	1318		
Slurry Wt. 14.8 - 15.0 PPG	1318	1330		
Water/Cement 6.25 Gal/SK				
Water Temp. 64°F				
Total Slurry Vol. 11.0				
Landed Plug @ 775	PSI/Final Lift @ 350	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code		Sub Total
Displace W/ 58.9	BBLS H ₂ O	State CO 2.9%		Tax
Circulate 6	BBLS Cement			Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		42			
1214/1217		Bulk Truck		42/42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim, Adam, Chris, Evan, Steve

Received By Randy Case
Customer or His Agent