



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7288 • FAX (970) 353-7712

OUR INVOICE

600556

Date <u>7/3/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>35N-15H2</u>	Lease <u>Thomas</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (MAJOR #42)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL	
<u>Surface</u>	<u>9 5/8" CSB-36" 13 1/2" Hole</u>	<u>805</u>	
	Bottom of Surface	FL	
		<u>790</u>	
Plug	Plug Landed @ <u>749</u>	FL	Time On <u>11020</u>
Production	Pipe Landed @ <u>790</u>	FL	Plug Down <u>1945</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	<u>590</u>	SKS		
Poz. Mix				
Caicium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge <u>2070642</u>	<u>132</u>	Miles		
Fuel Surcharge <u>80012090</u>	<u>132</u>	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>1859-</u>	<u>1905-</u>	
Disp. Rate 5 BPM	Mixing	<u>1905-</u>	<u>1931</u>	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	<u>1931-</u>	<u>1934</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>1934-</u>	<u>1945</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>76° F</u>				
Total Slurry Vol. <u>38.7</u>	BBLs Cement			
Landed Plug @ <u>600</u>	PSI/Final Lift @ <u>300</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>57.8</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>6</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>			
<u>1217/1218</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Evan, Steve & Marcos

Received By Ram
Customer or His Agent