



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600596

Date <u>7/27/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>16N-32 H2</u>	Lease <u>Sapchet</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 / MAJOR #420</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>800</u>	
<u>Surface</u> <u>9 5/8" CSG-36" 13 1/2" Hole</u>	Bottom of Surface	Ft. <u>796</u>	
Plug	Plug Landed @ <u>754</u>	Ft. Time On <u>0115</u>	
Production	Pipe Landed @ <u>796</u>	Ft. Plug Down <u>0345</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neal <u>✓ Type III</u>	<u>590</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	<u>132</u>	Miles		
Fuel Surcharge	<u>132</u>	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>0258-</u>	<u>0304</u>	
Disp. Rate 5 BPM	Mixing	<u>0304-</u>	<u>0330</u>	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	<u>0330-</u>	<u>0333</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>0333-</u>	<u>0345</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>74°F</u>				
Total Slurry Vol. <u>138.7</u>	BBLs Cement			
Landed Plug @ <u>300</u>	PSI/Final Lift @ <u>150</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>58.2</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1308</u>		Pump Truck		<u>44</u>			<u>2067732</u>
<u>124/1217</u>		Bulk Truck		<u>44/44</u>			<u>800/2090</u>

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Roon

Received By Randy Cude
Customer or His Agent