



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600547

Date	7-16-12	Well Owner	Kerr McGee	Well No.	37N-E3H2	Lease	CANNON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	Ft. 800			
Surface	9 5/8" CSG-36# 13 1/4" HX		Bottom of Surface	Ft. 793			
Plug			Plug Landed @	748	FL	Time On	1300
Production			Pipe Landed @	793	FL	Plug Down	1515

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Nest TYPE III	590	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1420	1425	
Disp. Rate 5 BPM	Mixing	1425	1500	
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1500	1503	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1503	1515	
Water/Cement 6.25 Gal/SK				
Water Temp. 73°F				
Total Slurry Vol. 138.7	BBLs Cement			
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 20	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ 57.8	BBLs H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate 4	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1214/1216		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH Z., ERNIE, JOSH A.

Received By

*Randy Cole*

Customer or His Agent

2072091