

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400342015

Date Received:

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 96850
2. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC
3. Address: 1001 17TH STREET - SUITE #1200
City: DENVER State: CO Zip: 80202
4. Contact Name: Sandra Salazar
Phone: (303) 629-8456
Fax: (303) 629-8268

5. API Number 05-045-21052-00
6. County: GARFIELD
7. Well Name: Duggan
Well Number: RWF 511-32
8. Location: QtrQtr: NENW Section: 32 Township: 6S Range: 94W Meridian: 6
9. Field Name: RULISON Field Code: 75400

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 03/23/2012 End Date: Date of First Production this formation: 03/26/2012

Perforations Top: 6043 Bottom: 7887 No. Holes: 124 Hole size: 0.35

Provide a brief summary of the formation treatment: Open Hole: ☐

3505 Gals 7 1/2% HCL; 638300 # 30/50 Sand; 195800 100/Mesh; 21914 Bbls Slickwater (Summary)

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 21997

Max pressure during treatment (psi):

Total gas used in treatment (mcf):

Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment:

Min frac gradient (psi/ft): 0.79

Total acid used in treatment (bbl): 83

Number of staged intervals: 6

Recycled water used in treatment (bbl): 21914

Flowback volume recovered (bbl): 12598

Fresh water used in treatment (bbl):

Disposition method for flowback: RECYCLE

Total proppant used (lbs): 834100

Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 04/29/2012 Hours: 24 Bbl oil: 0 Mcf Gas: 897 Bbl H2O: 0
Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 897 Bbl H2O: 0 GOR: 0
Test Method: Flowing Casing PSI: 2369 Tubing PSI: 2274 Choke Size: 8/64
Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1047 API Gravity Oil: 0
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7695 Tbg setting date: 04/17/2012 Packer Depth:
Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

- All flowback water entries are total estimates based on commingled volumes.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Sandra Salazar

Title: Permit Technician II Date: _____ Email: sandra.salazar@wpenergy.com
:

Attachment Check List

Att Doc Num	Name
400342230	WELLBORE DIAGRAM

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)