

Bayswater – Apollo 2012-2013 Drilling Program

Well Name: Bayswater River Bluffs 18-13

Surface Location: 1758 FNL 1452 FEL, SWNE 13 T6N R68W, Larimer Co, Colorado

Estimated BHL: 1374 FNL 1321 FWL, CNW 13 T6N R68W

Estimated Elevation: GR 4802, KB 4818

Estimated Surface Casing: 720

Estimated TD: 6920

<u>Formation</u>	<u>Depth (KB)/ (Struct)</u>	<u>Estimated Measured Depth (KB)</u>
Larimer (Parkman)	2948/1870	3172
Terry (Sussex)	3663/1155	3974
Hygiene (Shannon)	4053/765	4411
Niobrara	6433/-1615	6979
Fort Hays	6746/-1928	7292
Codell	6768/-1950	7314
Greenhorn	6818/-2000	7364
Graneros	6906/-2088	7452
TD	6920	7466

Primary Objectives: Niobrara A, B, C, Codell

Secondary Objectives: Greenhorn, Hygiene, Terry

Logging Coverage: TD to Surface (GR/Ind)
TD to 2650' (CNL/FDC)

Cement Coverage: TD to 2650'