

FORM

2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400317553

Date Received:

08/24/2012

PluggingBond SuretyID

20080034

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
 SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐Sidetrack ☐3. Name of Operator: BAYSWATER EXPLORATION AND PRODUCTION LLC4. COGCC Operator Number: 102615. Address: 730 17TH ST STE 610City: DENVER State: CO Zip: 802026. Contact Name: Corina Santos Phone: (303)928- Fax: (303)962-6237Email: csantos@petro-fs.com7. Well Name: Casa Loma Well Number: 4-25

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7542

WELL LOCATION INFORMATION

10. QtrQtr: NENE Sec: 26 Twp: 7N Rng: 67W Meridian: 6Latitude: 40.550919Longitude: -104.851560

Footage at Surface: 527 feet FNL/FSL 186 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 9075012. Ground Elevation: 4954 13. County: WELD

14. GPS Data:

Date of Measurement: 05/21/2012 PDOP Reading: 1.8 Instrument Operator's Name: Brian Ritz/PFS15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 780 FNL 556 FWL 657 FNL 655 FWL 657
 Sec: 25 Twp: 7N Rng: 67W Sec: 25 Twp: 7N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☒ Yes ☐ No17. Distance to the nearest building, public road, above ground utility or railroad: 189 ft18. Distance to nearest property line: 189 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 833 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Codell	CODL		80	N2NW
Greenhorn	GRNHN		80	N2NW
Niobrara	NBRR		80	N2NW
Shannon	SNSD		80	N2NW
Sussex	SUSX		80	N2NW

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

NE/4 of Section 26, Township 7 North, Range 67 West & Sec 25:NW/4 160 acres

25. Distance to Nearest Mineral Lease Line: 186 ft 26. Total Acres in Lease: 160

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	720	504	720	0
1ST	7+7/8	4+1/2	11.6	0	7,542	879	7,542	3,250

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Exception Location Waiver, per COGCC Rule 318A.c., has been mailed to the surface owner; once received the waiver will be sent to the COGCC.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Corina Santos

Title: Regulatory Technician Date: 8/24/2012 Email: csantos@petro-fs.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 11/4/2012

API NUMBER

05 123 36261 00

Permit Number: _____ Expiration Date: 11/3/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

E-mailed opr for status on permits.

Operator must meet Water Well Testing requirements as per amended Rule 318Ae(4)

- 1) Submit Form 42 electronically to COGCC 48 hours prior to MIRU..
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Shannon to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
1669164	LEGAL/LEASE DESCRIPTION
1699095	EXCEPTION LOC REQUEST
1699096	EXCEPTION LOC WAIVERS
400317553	FORM 2 SUBMITTED
400317565	DIRECTIONAL DATA
400317567	DEVIATED DRILLING PLAN
400317568	DRILLING PLAN
400317571	TOPO MAP
400317573	WELL LOCATION PLAT
400319971	30 DAY NOTICE LETTER
400320390	SURFACE AGRMT/SURETY

Total Attach: 11 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Attached lease as per opr and added comment to describe lease. Final review complete.	11/1/2012 8:59:25 AM
Permit	Operator requests approval of a Rule 318Aa and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location. Request and waivers attached. Need Mineral lease document for sect 25 NWNW	10/31/2012 9:39:54 AM
Permit	Form on hold for completion of form 2A	10/10/2012 7:39:14 AM
Permit	Final Review Completed. No LGD or public comment received.	9/20/2012 11:32:05 AM
Permit	Attached exception loc request and waiver as per opr.	9/18/2012 1:51:37 PM
Permit	On hold for exception location request and waiver.	8/27/2012 9:55:38 AM

Total: 6 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Planning	When feasible develop multiple well sites by using directional drilling to reduce cumulative impacts and adverse impacts on wildlife resources.
Drilling/Completion Operations	When available and reasonable use a closed-loop drilling mud system to preclude the use of an earthen reserve pits when available.
Site Specific	<p>Fence the well site after drilling to restrict public and wildlife access.</p> <p>Keep well site location, the road, and the pipeline easement free of noxious weeds, litter and debris.</p> <p>Spray for noxious weeds, and implement dust control, as needed.</p> <p>Operator will not permit the release or discharge of any toxic or hazardous chemicals or wastes on Owner's Land.</p> <p>Construct and maintain gates where any roads used by operator, its employees, or contractors cross through fences on the leased premises.</p>
Storm Water/Erosion Control	<p>Use water bars, and other measures to prevent erosion and non-source pollution.</p> <p>Implement and maintain BMPs to control stormwater runoff in a manner that minimizes erosion, transport of sediment offsite, and site degradation.</p> <p>Co-locate gas and water gathering lines whenever feasible, and mitigate any erosion problems that arise due to the construction of any pipeline(s).</p>
Construction	<p>Remove only the minimum amount of vegetation necessary for the construction of roads and facilities.</p> <p>Conserve topsoil during excavation and reuse as cover on disturbed areas to facilitate regrowth of vegetation.</p> <p>No construction or routine maintenance activities will be performed during periods when the soil is too wet to adequately support construction equipment.</p>
Interim Reclamation	<p>Utilize only such area around each producing well as is reasonably necessary.</p> <p>Restore the remainder of the well site location to its original condition within a reasonable time after the completion of operations.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p>
Final Reclamation	<p>All surface restoration shall be accomplished to the satisfaction of Owner.</p> <p>All reseeding shall be done with grasses consistent with the Rocky Mountain native mix or other grasses reasonably requested by surface owner and during planting period suggested by Owner.</p> <p>Final reclamation shall be completed to the reasonable satisfaction of the Owner as soon as practical after installation (weather permitting) and in accordance with regulatory agency standards (BLM/COGCC).</p>

Total: 7 comment(s)