

**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**200644**


Date <b>8/23/12</b>	Well Owner <b>Great Western</b>	Well No. <b>25-23</b>	Lease <b>GW</b>
County <b>Weld</b>	State <b>Colorado</b>	Field	
Charge to <b>CADE Drilling, LLC</b>	Charge Code		For Office Use Only
Address <b>3450 WCR 27 #2 (CADE #25)</b>			
City, State <b>FT. Lupton Colorado 80621</b>			
Pump Truck No. <b>1208</b>	Code	Bulk Truck No. <b>BM/BLK</b>	Code
Type of Job	Depth	Ft. <b>743</b>	To
<b>(Surface) 8 5/8" C93-24 #</b>	Bottom of Surface	Ft. <b>732</b>	To
Plug	Plug Landed @ <b>690</b>	Ft.	Time On <b>1415</b>
Production	Pipe Landed @ <b>732</b>	Ft.	Time Off <b>Plug Down @ 1845</b>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount	
	Pump Truck Charge					
	Cement Neat ✓	520	SKS			
	Poz. Mix					
	Calcium Chloride	3%				
	Gel % Flo-Cele <u>4</u> #Per Sack					
	Handling Charge					
	Hauling Charge					
	Additional Cement					
8 5/8"	Centralizers	3		70 <sup>00</sup>		
"	Cement Basket	1				
"	Guide Shoe	1				
"	Baffle Plate	1				
	Box-thread lock	1				
	Mix Rate 4 BPM	Slurry Vol - 1.18 FT <sup>3</sup> /SK - Water Temp - 5				
	Disp Rate 5 BPM	Slurry WT 15.2 PPG				
	Plug landed @ 500 PSI	Total Slurry Vol - 109.2 BBL Cement				
Remarks:	Pre-Flush w/ 20 BBL H <sub>2</sub> O	Tax Reference Code	Sub Total			
	Displace w/ 43.8 BBL H <sub>2</sub> O	State CO 29 %	Tax			
	Circulate 5 BBL Cement	Disc.	Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Ott
1208		Pump Truck		30		
BM/BLK		Bulk Truck		30/30		

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to r

Delivered By **Justin, Evan & Steve**

Received By

  
Customer