



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601131

Date	10-23-12	Well Owner	Kerr McGee	Well No.	25-2	Lease	CAMENISCH
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	934		
Surface	8 5/8" CS-24#	Bottom of Surface		Fl.	924		
Plug		Plug Landed @	878	Fl.	Time On	1945	
Production		Pipe Landed @	924	Fl.	Plug Down	2315	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	580	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	192	Miles		
Fuel Surcharge	192	miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	2219 - 2227	
Disp. Rate	5 BPM	Mixing	2227 - 2301	
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	2301 - 2304	
Slurry Wt.	14.8 - 15.0 PPG	Displacement	2304 - 2315	
Water/Cement	6.25 Gal/SK			
Water Temp.	55°F			
Total Slurry Vol.	1.36+3	BBLS Cement		
Landed Plug @	400	PSI/Final Lift @	380	PSI
Pre-Flush W/	30	BBLS H ₂ O	Tax Refundable Credit	Sub Total
Displace W/	55.8	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		64			
1214/1218		Bulk Truck		64/64			

WBS/WO/CC 2045967 DEL

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE JOSH Z., GRNIE

Received By

G/L Acct.

Customer or His Agent