



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600477

Date	4-10-12	Well Owner	Kerr McGee	Well No.	26N-29H2	Lease	WARDELL
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	925		
Surface	9 5/8" CSG-36# 13 1/2" H2E	Bottom of Surface		Fl.	914		
Plug		Plug Landed @	8'71	Fl.	Time On	2200	
Production		Pipe Landed @	9'14	Fl.	Plug Down	0030	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	680	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	150	Miles		
Fuel Surcharge	150	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	2325	2333
Disp. Rate	5 BPM	Mixing	2333	0013
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	0013	0016
Slurry WL	14.8 - 15.0 PPG	Displacement	0016	0030
Water/Cement	6.25 Gal/SK			
Water Temp.	62°F			
Total Slurry Vol.	159.8	BBLS Cement		
Landed Plug @	800	PSI/Final Lift @ 300	PSI	
Pre-Flush W/	30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	67.3	BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		50			
1214/1217		Bulk Truck		50/50		2066	397

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH Z., ERNIE, JOSH A.

Received By Randy Hall  
Customer or His Agent

80012090