

FORM
5A

Rev
06/12

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400303462

Date Received:

11/06/2012

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 16700
2. Name of Operator: CHEVRON USA INC
3. Address: 6001 BOLLINGER CANYON RD
City: SAN RAMON State: CA Zip: 94583
4. Contact Name: Julie Justus
Phone: (970) 257-6042
Fax: (970) 245-6489

5. API Number 05-045-17301-00
6. County: GARFIELD
7. Well Name: SKR-698-09-AV
Well Number: 06
8. Location: QtrQtr: SENE Section: 9 Township: 6S Range: 98W Meridian: 6
9. Field Name: SKINNER RIDGE Field Code: 77548

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 03/25/2012 End Date: 04/02/2012 Date of First Production this formation: 04/06/2012

Perforations Top: 3647 Bottom: 5873 No. Holes: 243 Hole size: 0.35

Provide a brief summary of the formation treatment: Open Hole: ☐

Pumped a total of 1,547,923 gal of clean water and 967,864 lbs of sand in 9 stages to fracture WF/Cameo formation

This formation is commingled with another formation: ☐ Yes ☒ No

Total fluid used in treatment (bbl): 36855 Max pressure during treatment (psi): 6237

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.75

Total acid used in treatment (bbl): Number of staged intervals: 9

Recycled water used in treatment (bbl): 32793 Flowback volume recovered (bbl): 16014

Fresh water used in treatment (bbl): 4062 Disposition method for flowback: RECYCLE

Total proppant used (lbs): 967864 Rule 805 green completion techniques were utilized: ☒

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 04/14/2012 Hours: 24 Bbl oil: 0 Mcf Gas: 293 Bbl H2O: 1351

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 293 Bbl H2O: 1351 GOR: 0

Test Method: Flowing Casing PSI: 1380 Tubing PSI: 440 Choke Size: 32/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1086 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 5015 Tbg setting date: 04/12/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

** Bridge Plug Depth: ** Sacks cement on top: ** Wireline and Cement Job Summary must be attached.

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie Justus

Title: Regulatory Specialist Date: 11/6/2012 Email jjustus@chevron.com
:

Attachment Check List

Att Doc Num	Name
400303462	FORM 5A SUBMITTED
400321700	WELLBORE DIAGRAM

Total Attach: 2 Files

General Comments

User Group **Comment** **Comment Date**

--	--	--

Total: 0 comment(s)