

FORM 5A

Rev 06/12

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Table with columns DE, ET, OE, ES

Document Number: 400321378

Date Received: 11/05/2012

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 16700
2. Name of Operator: CHEVRON USA INC
3. Address: 6001 BOLLINGER CANYON RD
City: SAN RAMON State: CA Zip: 94583
4. Contact Name: Julie Justus
Phone: (970) 257-6042
Fax: (970) 245-6393

5. API Number 05-045-17297-00
6. County: GARFIELD
7. Well Name: SKR-698-09-AV
Well Number: 01
8. Location: QtrQtr: SENE Section: 9 Township: 6S Range: 98W Meridian: 6
9. Field Name: SKINNER RIDGE Field Code: 77548

Completed Interval

FORMATION: WILLIAMS FORK - CAMEO Status: PRODUCING Treatment Type: FRACTURE STIMULATION

Treatment Date: 04/15/2012 End Date: 06/24/2012 Date of First Production this formation: 04/17/2012

Perforations Top: 4140 Bottom: 6415 No. Holes: 240 Hole size: 0.35

Provide a brief summary of the formation treatment: Open Hole: [ ]

Pumped a total of 1,507,926 gal of clean produced water and 925,370 lbs sand in 9 stages to fracture WF/Cameo formation..

This formation is commingled with another formation: [ ] Yes [X] No

Total fluid used in treatment (bbl): 35903 Max pressure during treatment (psi): 6492

Total gas used in treatment (mcf): Fluid density at initial fracture (lbs/gal): 8.43

Type of gas used in treatment: Min frac gradient (psi/ft): 0.75

Total acid used in treatment (bbl): Number of staged intervals: 9

Recycled water used in treatment (bbl): 35903 Flowback volume recovered (bbl): 20436

Fresh water used in treatment (bbl): Disposition method for flowback: RECYCLE

Total proppant used (lbs): 925370 Rule 805 green completion techniques were utilized: [X]

Reason why green completion not utilized:

Fracture stimulations must be reported on FracFocus.org

Test Information:

Date: 07/17/2012 Hours: 24 Bbl oil: 0 Mcf Gas: 1282 Bbl H2O: 539

Calculated 24 hour rate: Bbl oil: 0 Mcf Gas: 1282 Bbl H2O: 539 GOR: 0

Test Method: Flowing Casing PSI: 1520 Tubing PSI: 920 Choke Size: 24/64

Gas Disposition: SOLD Gas Type: DRY Btu Gas: 1086 API Gravity Oil: 0

Tubing Size: 2 + 3/8 Tubing Setting Depth: 5994 Tbg setting date: 07/16/2012 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: [ ] Yes [ ] No If yes, number of sacks cmt

\*\* Bridge Plug Depth: \*\* Sacks cement on top: \*\* Wireline and Cement Job Summary must be attached.

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julie Justus

Title: Regulatory Specialist Date: 11/5/2012 Email: jjustus@chevron.com  
:

### **Attachment Check List**

Att Doc Num	Name
400321378	FORM 5A SUBMITTED
400321386	WELLBORE DIAGRAM

Total Attach: 2 Files

### **General Comments**

**User Group**      **Comment**      **Comment Date**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)