

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400325233

Date Received:

09/10/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: JOEL MALEFYT

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6828

3. Address: P O BOX 173779

Fax: (720) 929-7828

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33819-00

6. County: WELD

7. Well Name: DACONO

Well Number: 5-2

8. Location: QtrQtr: SENW Section: 2 Township: 1N Range: 68W Meridian: 6

Footage at surface: Distance: 2108 feet Direction: FNL Distance: 1861 feet Direction: FWL

As Drilled Latitude: 40.081898 As Drilled Longitude: -104.973288

GPS Data:

Data of Measurement: 04/17/2012 PDOP Reading: 1.3 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 1973 feet. Direction: FNL Dist.: 657 feet. Direction: FWL

Sec: 2 Twp: 1N Rng: 68W

** If directional footage at Bottom Hole Dist.: 1969 feet. Direction: FNL Dist.: 655 feet. Direction: FWL

Sec: 2 Twp: 1N Rng: 68W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/13/2012 13. Date TD: 03/17/2012 14. Date Casing Set or D&A: 03/18/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8468 TVD** 8321 17 Plug Back Total Depth MD 8412 TVD** 8265

18. Elevations GR 5017 KB 5032

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

P/E AILC-CNLD-ML-TC; CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	947	600	0	947	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,458	41	8,284	8,458	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: 03/18/2012					
Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	8,218	1,016	1,150	8,218
Details of work:					

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,242		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,674	4,953	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,607		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,900		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,333		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JOEL MALEFYT
 Title: REGULATORY ANALYST Date: 9/10/2012 Email: JOEL.MALEFYT@ANADARKO.COM

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400325238	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400325237	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400325233	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400325236	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group **Comment** **Comment Date**

--	--	--

Total: 0 comment(s)