



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 37055
LOCATION Oakley, KS
FOREMAN Kelly Gabel

CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-1-12	9160	Manalo #3	39	105	55 ⁰⁰	Lincoln
CUSTOMER Wheipking Fullerton						
MAILING ADDRESS						
CITY			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Damon M		
			566	Wes F		
STATE						
ZIP CODE						
JOB TYPE						

JOB TYPE <u>Surface</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>305</u>	CASING SIZE & WEIGHT <u>8 5/8 24.7</u>
CASING DEPTH <u>298</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>148</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>20</u>
DISPLACEMENT <u>17 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE _____

REMARKS: safety meeting, rigged up on 3/4" drill pipe, hooked up to
circulate, mixed 155 lbs Cem 3% CC 2% gel, released plug, displaced
with 1 1/2 bbl water, shut in

Cement did circulate

APPROX. 7000 TO PIT

Thank You
Kelly & crew

[illegible]

Bayin 3737

4:00 PM

AUTHORIZATION

TITLE DRUG SUPPLY

DATE 8-1-12

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

151785



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

TICKET NUMBER 37190
LOCATION Oakley Ks
FOREMAN Walt Diuka

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-5-12	9160	Makalo #3	29	103	55W	Lincoln
CUSTOMER Wierking - Fullerton			21mon C			
MAILING ADDRESS			TRUCK #	DRIVER	TRUCK #	DRIVER
CITY			55	456-T118		
STATE			1 E	530-T129		
ZIP CODE			1/4N			

JOB TYPE Prod HOLE SIZE 7 7/8 HOLE DEPTH 17900' CASING SIZE & WEIGHT 5 1/2 - 17 #
CASING DEPTH 7898 DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT 14.2 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT 182 DISPLACEMENT PSI _____ MIX PSI _____ RATE 7 BPM

REMARKS: Safety Meeting, Vis up on Murem #25, run Float Equipment
Centralizers on 1, 2, 4, 15, 16, 17, 18, 19, 20, 21, 22, 23, 80, 82, Baskets on #2-81
Port Collar on #81, Circ 2 100 Hts in and on Bottom, Pumped 500 gal mud Flush
Mixed 10 sk in Rott, 10 sks in Mott, mixed 260 sks H₂O, 10% salt, 5# Kalsol
296 gal, 1/4# FlorSeal, clear Pump + Lines, release Plug + Displace 185 H₂O
2 1100# Pressure, Landed Plug, 2 1600#, release Pressure, Float Held

Thank You
Walt + crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	4050 ⁰⁰	4050 ⁰⁰
5406	100	MILEAGE	5 ⁰⁰	500 ⁰⁰
1115A	280 SKS	Class "H" Cement	19 ³⁰	5,404 ⁰⁰
1111	1,339 #	Salt	1.45	602 ⁵⁵
1110A	1400 #	Kalsol	1.56	784 ⁰⁰
1118B	526 #	Gel	1.25	131 ⁵⁰
1107	70 #	FlorSeal	2 ⁸²	197 ⁴⁰
1144G	500 gal	mud Flush	1 ⁰⁰	500 ⁰⁰
5407A	13.16	Ton Mileage Delivery	167	2,197 ⁷²
4159	1	5 1/2 - AFU Float Shoe	413 ⁰⁰	413 ⁰⁰
4454	1	5 1/2 - Hatchdown Plug Assy	303 ⁰⁰	303 ⁰⁰
4136	12	5 1/2 - Turbo-Centralizers	72 ⁰⁰	864 ⁰⁰
4130	2	5 1/2 - Centralizers	58 ⁰⁰	116 ⁰⁰
4104	2	5 1/2 Baskets	276 ⁰⁰	552 ⁰⁰
4285	1	5 1/2 Port Collar	2,075 ⁰⁰	2,075 ⁰⁰
				18,690 ¹⁷
		Less 10% Disc		1,869 ⁰²
				16,821 ¹⁵
			SALES TAX	838 ³⁶
			ESTIMATED TOTAL	17,659 ⁵¹
			DATE	9/5/12

Ravin 3737

AUTHORIZATION Betsy Smith TITLE CC-man
I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

2521.43



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 37211
LOCATION Oakley Ks
FOREMAN Walt Dunkel

FIELD TICKET & TREATMENT REPORT

Celo

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-4-12	9160	Makala #3	29	10S	55W	Lincoln
CUSTOMER Wierking - Fullerton			Limon 5S			
MAILING ADDRESS						
CITY	STATE	ZIP CODE	TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Damon Miller		
			530-T129	Chris Meade		

JOB TYPE <u>Part Collar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2 - 17#</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8"</u>	OTHER <u>PC 4547'</u>
SLURRY WEIGHT <u>13.5</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING _____
DISPLACEMENT <u>25 1/2</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE <u>3 BPM @ 1100#</u>
REMARKS: <u>Safety Meeting, rig up equipment, open Test Casing to 1500#</u> <u>Open Tool, Pump down tubing, Pressured to 1500# Hold, Brake Circ</u> <u>Pump into @ 3 BPM @ 1100#, mixed 250 sks 60% opz, 6% cal, 2% cc,</u> <u>1/4# Flo Seal, Displace w/ 25 1/2 BBL H2O, Shut Tool, Test to 1500# Hold</u> <u>Circ. KCL Water Thruout.</u>			

Thank You
Walt & Crew

[illegible]

AUTHORIZATION Lorenzo Baccalini TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form