

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400321636

Date Received:

08/28/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100185

4. Contact Name: Marina Ayala

2. Name of Operator: ENCANA OIL & GAS (USA) INC

Phone: (720) 876-5905

3. Address: 370 17TH ST STE 1700

Fax: (720) 876-6905

City: DENVER State: CO Zip: 80202-

5. API Number 05-045-20439-00

6. County: GARFIELD

7. Well Name: DW

Well Number: 8608A-33 P28496

8. Location: QtrQtr: SESE Section: 28 Township: 4S Range: 96W Meridian: 6

Footage at surface: Distance: 544 feet Direction: FSL Distance: 446 feet Direction: FEL

As Drilled Latitude: 39.667555 As Drilled Longitude: -108.165715

GPS Data:

Data of Measurement: 12/12/2011 PDOP Reading: 2.4 GPS Instrument Operator's Name: Brandon Birdsall

** If directional footage at Top of Prod. Zone Dist.: 1352 feet. Direction: FNL Dist.: 1262 feet. Direction: FEL
Sec: 33 Twp: 4S Rng: 96W

** If directional footage at Bottom Hole Dist.: 1375 feet. Direction: FNL Dist.: 1343 feet. Direction: FEL
Sec: 33 Twp: 4S Rng: 96W

9. Field Name: WILDCAT

10. Field Number: 99999

11. Federal, Indian or State Lease Number: COC65556

12. Spud Date: (when the 1st bit hit the dirt) 07/04/2011 13. Date TD: 08/22/2011 14. Date Casing Set or D&A: 08/24/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11945 TVD** 11611 17 Plug Back Total Depth MD 11888 TVD** 11553

18. Elevations GR 7791 KB 7813

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

RST, CBL (included in Triple Combo) and Mud.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	30	20	42	0	118	239	0	118	CALC
SURF	14+3/4	9+5/8	36	0	2,095	774	0	2,120	CALC
1ST	8+3/4	4+1/2	11.6	0	11,912	1,753	5,650	11,945	CBL

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
WILLIAMS FORK	7,202	10,972	<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	10,973	11,945	<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Marina Ayala

Title: Permitting Technician Date: 8/28/2012 Email: marina.ayala@encana.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400321651	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400321648	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400321636	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400321640	PDF-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400321642	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400321650	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

User Group	Comment	Comment Date
Permit	Requested digital CBL.	11/1/2012 2:16:33 PM

Total: 1 comment(s)