



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600594

Date <u>7/23/12</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>15N- W3H#</u>	Lease <u>(A220202)</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil &amp; Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (MAJOR #42)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>814</u>	
<u>Surface</u> <u>9 5/8" CSG-30" 13 1/2" Hole</u>	Bottom of Surface	Ft. <u>799</u>	
Plug	Plug Landed @ <u>758</u>	Ft.	Time On <u>1800</u>
Production	Pipe Landed @ <u>799</u>	Ft.	Plug Down <u>2015</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>✓ Type III</u>	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cele 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	Miles		
Additional Cement	1	SKS		
Mixing Rate 4 BPM	Pre-Flush	1928-1934		
Disp. Rate 5 BPM	Mixing	1934-2000		
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	2000-2003		
Slurry Wt. 14.8 - 15.0 PPG	Displacement	2003-2015		
Water/Cement 6.25 Gal/SK				
Water Temp. <u>78°F</u>				
Total Slurry Vol. <u>141</u>	BBLs Cement			
Landed Plug @ <u>650</u>	PSI/Final Lift @ <u>300</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ <u>58.5</u>	BBLs H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate <u>4</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>			
<u>1217/124</u>		Bulk Truck		<u>44/44</u>			<u>2073/46 Dr 1</u>

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Ryan Steve

Received By Colin Sanders  
Customer or His Agent