



CEMENTER'S WELL-SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7289 • FAX (970) 353-7712

OUR INVOICE

600548

16N

Date	7-18-12	Well Owner	Kerr McGee	Well No.	16N-E3H2	Lease	CANNON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	812		
Surface	9 5/8" CSG-36" 13 1/2" 4IN	Bottom of Surface		Fl.	812		
Plug		Plug Landed @	778	Fl.	Time On	0845	
Production		Pipe Landed @	812	Fl.	Plug Down	1230	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Near TYPE III	610	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1134	1139
Disp. Rate	5 BPM	Mixing	1139	1215
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1215	1218
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1218	1230
Water/Cement	6.25 Gal/SK			
Water Temp.	76°F			
Total Slurry Vol.	143.4	BBLs Cement		
Landed Plug @	800	PSI/Final Lift @	300	PSI
Pre-Flush W/	20	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	60.1	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	6	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			2072092
1214/1217		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOSH C., JOE, JOSH A., MARCOS

Received By *Randy Cuse*
Customer or His Agent

80012090