



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600587

Date	10/9/12	Well Owner	Kerr McGee	Well No.	4N-9H2	Lease	Haymaker
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (major #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Fl. 930				
Surface	9 5/8 CSG 36" 13 1/2" Hole	Bottom of Surface	Fl. 924				
Plug		Plug Landed @	880	Fl.	Time On	1400	
Production		Pipe Landed @	924	Fl.	Plug Down	1630	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	690	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1528	1534	
Disp. Rate 5 BPM	Mixing	1534	1614	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	1614	1617	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1617	1630	
Water/Cement 6.25 Gal/SK				
Water Temp. 51°F				
Total Slurry Vol. 162.2	BBLs Cement			
Landed Plug @ 800	PSI/Final Lift @ 325			
Pre-Flush W/ 30	RRI S H ₂ O			
Displace W/ 68.0	BBLs H ₂ O			
Circulate 6	BBLs Cement			

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		44			
1214/1216		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By _____

Received By

Brian Ray

Customer or His Agent