



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600564

Date	7/5/2012	Well Owner	Kerr McGee	Well No.	13C-15H2	Lease	THOMASON
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR# 42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL	814			
Surface	9 5/8 C.S.G. 3" #	Bottom of Surface	FL	808			
Plug		Plug Landed @	766	FL	Time On	1220	
Production		Pipe Landed @	808	FL	Plug Down	1330	

Description	Qty.	Mess.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	600	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	2070686	132	Miles	
Fuel Surcharge	800/2090	132	MEILES	
Additional Cement			SKS	
Mixing Rate	4 BPM	Pre-Flush	1234	1240
Disp. Rate	5 BPM	Mixing	1240	1315
Slurry Vol.	1.32 <sup>3</sup> Cu.FL/Sk	Change Valves	1315	1318
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1318	1330
Water/Cement	6.25 Gal/SK			
Water Temp.	60			
Total Slurry Vol.	141.0	BBLs Cement		
Landed Plug @	790	PSI/Final Lift @	250	PSI
Pre-Flush W/	30	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	59.2	BBLs H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	4	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		44			
1214/1218		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/CHRS

Received By Randy Case  
Customer or His Agent