



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 600581

Date	7/15/12	Well Owner	Kerr McGee	Well No.	1N-11H2	Lease	Weiche1
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Major #42)						
City, State Zip	Denver, Colorado 80202						
Type of Job			Depth	FL 940			
Surface	9 5/8" CSG 36 # 13 1/2" Hole		Bottom of Surface	FL 934			
Plug			Plug Landed @	889	FL	Time On 1045	
Production			Pipe Landed @	934	FL	Plug Down 1315	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	700	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % / Flo-Cete 1/4 # Per Sack				
Mileage Charge	144	Miles		
Fuel Surcharge 2066667	144	miles		
Additional Cement 800/2090		SKS		
Mixing Rate	4 BPM	Pre-Flush	1212	1218
Disp. Rate	5 BPM	Mixing	1218	1259
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1259	1302
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1302	1315
Water/Cement	6.25 Gal/SK			
Water Temp.	72°F			
Total Slurry Vol.	164.5	BBLS Cement		
Landed Plug @	850	PSI/Final Lift @	375	PSI
Pre-Flush W/	30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	68.7	BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		48			
1214/1216		Bulk Truck		48/48			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Adam, Steven, Chris, Marco

Received By Randy Case  
Customer or His Agent