



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

600584

Date <u>7/26/2012</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>37N-32HZ</u>	Lease <u>SARCHET</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700</u>	<u>(MAJOR # 42)</u>		
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job <u>9 5/8" CSG 32" 13 1/2" Hole</u>	Depth <u>71 Cu. Ft.</u>	FL <u>811</u>	
Surface <u>9 5/8" CSG 32" 13 1/2" Hole</u>	Bottom of Surface	FL <u>796</u>	
Plug	Plug Landed @ <u>754</u>	Time On <u>0345</u>	
Production	Pipe Landed @ <u>796</u>	Plug Down <u>0600</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>590</u>	SKS		
Poz. Mix				
Calcium Chloride	<u>2.5</u>	%		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge	<u>132</u>	Miles		
Fuel Surcharge	<u>132</u>	miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>0509</u>	<u>0511</u>	
Disp. Rate 5 BPM	Mixing	<u>0511</u>	<u>0546</u>	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	<u>0546</u>	<u>0549</u>	
Slurry WL 14.8 - 15.0 PPG	Displacement	<u>0549</u>	<u>0600</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>63</u>				
Total Slurry Vol. <u>139.7</u>	BBLs Cement			
Landed Plug @ <u>750</u>	PSI/Final Lift @ <u>290</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>58.2</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>44</u>			
<u>1217/1218</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim Adams/CHRS

Received By [Signature]

Customer or His Agent

2067729.00
2090