



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7258 • FAX (970) 353-7712

OUR INVOICE

## 600545

Date	7-13-12	Well Owner	Kerr McGee	Well No.	26-11H2	Lease	WEICHEL
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR H42)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	930		
Surface	9 5/8" CSO-36H 13 1/2" HOLE	Bottom of Surface		Fl.	925		
Plug		Plug Landed @	881	Fl.	Time On	0645	
Production		Pipe Landed @	925	Fl.	Plug Down	1045	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	690	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0939	0947
Disp. Rate	5 BPM	Mixing	0947	1028
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1028	1031
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1031	1045
Water/Cement	6.25 Gal/SK			
Water Temp.	71°F			
Total Slurry Vol.	162.2	BBLS Cement		
Landed Plug @	800	PSI/Final Lift @ 300	PSI	
Pre-Flush Wt 30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace Wt 68.1	BBLS H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate 6	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
1214/1217		Bulk Truck		44/44			2066668

80012090

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH Z., ERNIE, JOSH A.

Received By

*[Signature]*  
Customer or His Agent