

FORM
5

Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400345526

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10071

4. Contact Name: Julie Webb

2. Name of Operator: BARRETT CORPORATION* BILL

Phone: (303) 312-8714

3. Address: 1099 18TH ST STE 2300

Fax: (303) 291-0420

City: DENVER State: CO Zip: 80202

5. API Number 05-123-35773-00

6. County: WELD

7. Well Name: 70 Ranch

Well Number: 5-63-22-58H

8. Location: QtrQtr: NENE Section: 22 Township: 5N Range: 63W Meridian: 6

Footage at surface: Distance: 250 feet Direction: FNL Distance: 660 feet Direction: FEL

As Drilled Latitude: 40.391390 As Drilled Longitude: -104.415110

GPS Data:

Data of Measurement: 11/19/2012 PDOP Reading: 4.8 GPS Instrument Operator's Name: Brian Rottinghaus

** If directional footage at Top of Prod. Zone Dist.: 599 feet. Direction: FNL Dist.: 643 feet. Direction: FEL

Sec: 22 Twp: 5N Rng: 63W

** If directional footage at Bottom Hole Dist.: 650 feet. Direction: FSL Dist.: 511 feet. Direction: FEL

Sec: 22 Twp: 5N Rng: 63W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number: COC063737

12. Spud Date: (when the 1st bit hit the dirt) 09/07/2012 13. Date TD: 09/19/2012 14. Date Casing Set or D&A: 09/22/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 10838 TVD** 6463 17 Plug Back Total Depth MD 10835 TVD** 6463

18. Elevations GR 4637 KB 4659

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL, triple Combo, mud

20. Casing, Liner and Cement:

CASING

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Top | Cmt Bot | Status |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|--------|
| CONDUCTOR | 24 | 16 | 45 | 0 | 60 | | 0 | 60 | CALC |
| SURF | 13+1/2 | 9+5/8 | 36 | 0 | 815 | 390 | 0 | 815 | CALC |
| 1ST | 8+3/4 | 7 | 26 | 0 | 6,810 | 570 | 1,074 | 6,820 | CBL |
| 1ST LINER | 6+1/8 | 4+1/2 | 11.6 | 0 | 10,838 | | | | |

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

| Method used | String | Cementing tool setting/perf depth | Cement volume | Cement top | Cement bottom |
|-------------|--------|-----------------------------------|---------------|------------|---------------|
| | | | | | |

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

| FORMATION NAME | Measured Depth | | Check if applies | | COMMENTS (All DST and Core Analyses must be submitted to COGCC) |
|----------------|----------------|--------|--------------------------|--------------------------|---|
| | Top | Bottom | DST | Cored | |
| NIOBRARA | 6,431 | | <input type="checkbox"/> | <input type="checkbox"/> | |

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Julie Webb

Title: Permit Analyst Date: _____ Email: jwebb@billbarrettcorp.com

Attachment Check List

| Att Doc Num | Document Name | attached ? | | | |
|-----------------------------|------------------------|------------|-------------------------------------|----|-------------------------------------|
| <u>Attachment Checklist</u> | | | | | |
| 400351319 | CMT Summary * | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | Core Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| 400351322 | Directional Survey ** | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | DST Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| | Logs | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | Other | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| <u>Other Attachments</u> | | | | | |
| 400345534 | LAS-CEMENT BOND | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400345537 | LAS-TRIPLE COMBINATION | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400345751 | LAS-MUD | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400351355 | DIRECTIONAL DATA | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
| | | |

Total: 0 comment(s)