



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

601085

Date	9-20-12	Well Owner	Kerr McGee	Well No.	27A-W9H	Lease	THOMASO
County		State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MATOR #44)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	930		
Surface	9 5/8" CSG-36# 1 3/4" HOPE	Bottom of Surface		Fl.	922		
Plug		Plug Landed @	8.777	Fl.	Time On	1345	
Production		Pipe Landed @	922	Fl.	Plug Down	1630	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	690	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1524	1532	
Disp. Rate 5 BPM	Mixing	1532	1613	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	1613	1616	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1616	1630	
Water/Cement 6.25 Gal/SK				
Water Temp. 65°F				
Total Slurry Vol. 162.2	BBLs Cement			
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 30	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 67.7	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate 4	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		44			
217/1218		Bulk Truck		44/144			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and inspection.

Delivered By JOE, JOSHIE, ERNIE, JOSH A.

Received By [Signature]
Customer or His Agent