



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**601098**

Date	10-7-12	Well Owner	Kerr McGee	Well No.	29N-942	Lease	HAYMAKER
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (major - 40)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	940		
Surface	9 5/8" - 36" - 13 1/2" Hole	Bottom of Surface		FL	928		
Plug		Plug Landed @	883	FL	Time On	1130	
Production		Pipe Landed @	928	FL	Plug Down	1445	
Description		Qty.	Meas.	Unit Price	Amount		
Set Up Charge		1					
Cement Neat	TYPE III	690	SKS				
Poz. Mix							
Calcium Chloride		2.5	%				
Gel % Flo-Crete 1/4 # Per Sack							
Mileage Charge		132	Miles				
Fuel Surcharge		132	MILES				
Additional Cement			SKS				
Mixing Rate	4 BPM	Pre-Flush	1339	-1347			
Disp. Rate	5 BPM	Mixing	1347	-1428			
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1428	-1431			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1431	-1445			
Water/Cement	6.25 Gal/SK						
Water Temp.	46°F						
Total Slurry Vol.	162.2	BBLS Cement					
Landed Plug @	800	PSI/Final Lift @	300	PSI	2008:33		
Pre-Flush W/	30	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	8001702		
Displace W/	68.2	BBLS H <sub>2</sub> O	State	CO 2.9%	Tax		
Circulate	4	BBLS Cement		Total			
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		94			
1216/1218		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By

Joe. JASHZ, ERNIE

Received By

Brian B.

Customer or His Agent