

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400340687

Date Received:

10/29/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Emily Carrender

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6282

3. Address: P O BOX 173779

Fax: (720) 929-7282

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-35359-00

6. County: WELD

7. Well Name: WEICHEL

Well Number: 30N-23HZ

8. Location: QtrQtr: SESE Section: 14 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 496 feet Direction: FSL Distance: 420 feet Direction: FEL

As Drilled Latitude: 40.132618 As Drilled Longitude: -104.623110

GPS Data:

Data of Measurement: 09/24/2012 PDOP Reading: 1.4 GPS Instrument Operator's Name: Renee Doiron

** If directional footage at Top of Prod. Zone Dist.: 79 feet. Direction: FNL Dist.: 603 feet. Direction: FEL

Sec: 14 Twp: 2N Rng: 65W

** If directional footage at Bottom Hole Dist.: 161 feet. Direction: FNL Dist.: 484 feet. Direction: FWL

Sec: 23 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 07/13/2012 13. Date TD: 08/11/2012 14. Date Casing Set or D&A: 08/13/2012

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11593 TVD** 6951 17 Plug Back Total Depth MD TVD**

18. Elevations GR 4879 KB 4895

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

PRE FORM 5

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36.0	0	940	700	16	940	CALC
1ST	8+3/4	7	26.0	0	7,388	707	16	7,388	CALC
1ST LINER	6+1/8	4+1/2	11.6	6418	11,578				CALC

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,919		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,090		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Emily CarrenderTitle: Operation Specialist I Date: 10/29/2012 Email: emily.carrender@anadarko.com**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400340696	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400340695	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400340687	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400340697	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Corrected BHL to section 23 (was 14).	11/19/2012 8:31:20 AM

Total: 1 comment(s)