

FORM
5Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400344608

Date Received:

11/13/2012

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: EILEEN ROBERTS

2. Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-34557-00

6. County: WELD

7. Well Name: SHOEMAKER PC A

Well Number: 12-69HN

8. Location: QtrQtr: NWNE Section: 12 Township: 6N Range: 64W Meridian: 6

Footage at surface: Distance: 337 feet Direction: FNL Distance: 2409 feet Direction: FEL

As Drilled Latitude: 40.507120 As Drilled Longitude: -104.497460

GPS Data:

Data of Measurement: 04/17/2012 PDOP Reading: 4.0 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: 120 feet. Direction: FNL Dist.: 1862 feet. Direction: FEL

Sec: 7 Twp: 6N Rng: 63W

** If directional footage at Bottom Hole Dist.: 38 feet. Direction: FSL Dist.: 1868 feet. Direction: FEL

Sec: 6 Twp: 6N Rng: 63W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 02/22/2012 13. Date TD: 03/01/2012 14. Date Casing Set or D&A: 03/04/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11919 TVD** 6689 17 Plug Back Total Depth MD 11676 TVD** 6446

18. Elevations GR 4720 KB 4744

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CBL/GRL/CCL/VDL.

No other logs sent at this time.

20. Casing, Liner and Cement:

CASING

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Top | Cmt Bot | Status |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|--------|
| CONDUCTOR | 18+1/2 | 16+0/0 | 84.00 | 0 | 124 | 160 | 0 | 124 | CALC |
| SURF | 13+3/4 | 9+5/8 | 36.00 | 0 | 867 | 418 | 0 | 877 | CALC |
| 1ST | 8+3/4 | 7+0/0 | 26.00 | 0 | 7,108 | 555 | 800 | 7,118 | CBL |
| 1ST LINER | 6+1/8 | 4+1/2 | 11.60 | 6793 | 11,731 | | | | |

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

| Method used | String | Cementing tool setting/perf depth | Cement volume | Cement top | Cement bottom |
|-------------|--------|-----------------------------------|---------------|------------|---------------|
| | | | | | |

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

| FORMATION NAME | Measured Depth | | Check if applies | | COMMENTS (All DST and Core Analyses must be submitted to COGCC) |
|----------------|----------------|--------|--------------------------|--------------------------|---|
| | Top | Bottom | DST | Cored | |
| SUSSEX | 4,422 | | <input type="checkbox"/> | <input type="checkbox"/> | |
| SHANNON | 5,124 | | <input type="checkbox"/> | <input type="checkbox"/> | |
| NIOBRARA | 6,736 | | <input type="checkbox"/> | <input type="checkbox"/> | |

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: 11/13/2012 Email: eroberts@nobleenergyinc.com

Attachment Check List

| Att Doc Num | Document Name | attached ? | | | |
|-----------------------------|-----------------------|------------|-------------------------------------|----|-------------------------------------|
| <u>Attachment Checklist</u> | | | | | |
| 400344978 | CMT Summary * | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | Core Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| 400344981 | Directional Survey ** | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | DST Analysis | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| | Logs | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| | Other | Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
| <u>Other Attachments</u> | | | | | |
| 400344608 | FORM 5 SUBMITTED | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400344976 | CEMENT BOND | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
| 400350760 | DIRECTIONAL DATA | Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|--------------------------|--|----------------------------|
| Permit | Off Hold per operator corrected directional information and lat/long. | 11/27/2012 2:27:15 PM |
| Permit | On Hold. Requested as built information and corrected directional template | 11/27/2012 12:22:57 PM |

Total: 2 comment(s)