

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400346162

Date Received:

11/14/2012

APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

2. TYPE OF WELL

OIL  GAS  COALBED  OTHER \_\_\_\_\_  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20100017

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Bonnie Lamond Phone: (720)876-5156 Fax: (720)876-6177

Email: bonnie.lamond@encana.com

7. Well Name: Shideler Well Number: 30-3A (O19EB)

8. Unit Name (if appl): Hunter Mesa Unit Number: COC055972  
X

9. Proposed Total Measured Depth: 7888

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 19 Twp: 7S Rng: 92W Meridian: 6

Latitude: 39.426129 Longitude: -107.705223

Footage at Surface: 569 feet FNL/FSL FSL 1658 feet FEL/FWL FEL

11. Field Name: Mamm Creek Field Number: 52500

12. Ground Elevation: 6509 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 06/08/2010 PDOP Reading: 0.0 Instrument Operator's Name: Ted T. Taggart

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 162 FNL 2127 FEL FEL Bottom Hole: FNL/FSL 162 FNL 2127 FEL FEL  
Sec: 30 Twp: 7S Rng: 92W Sec: 30 Twp: 7S Rng: 92W

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 1400 ft

18. Distance to nearest property line: 671 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 400 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK			

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
 T7S-R92W Sec 19: S2NE, SENW, SE Sec 30: Lots 1, 2, E2W2, W2E2

25. Distance to Nearest Mineral Lease Line: 506 ft                      26. Total Acres in Lease: 638

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated?     Yes                       No    If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?     Yes                       No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?     Yes                       No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?     Yes                       No

31. Mud disposal:     Offsite                       Onsite                      **If 28, 29, or 30 are "Yes" a pit permit may be required.**

Method:     Land Farming                       Land Spreading                       Disposal Facility                      Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	42	0	40	90	40	0
SURF	14+3/4	9+5/8	36	0	1,094	415	1,094	0
1ST	8+3/4	4+1/2	11.6	0	7,888	585	7,888	0

32. BOP Equipment Type:     Annular Preventer                       Double Ram                       Rotating Head                       None

33. Comments    This is a tapered hole: 14.75" hole to 200' MD, 12.25" hole to surface TD. 8.75" hole to top of gas, 7.875" hole to TD. TOC will be 500 feet above TOG. Nearest building is 1400 feet away.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ?     Yes                       No

36. Is this application part of submitted Oil and Gas Location Assessment ?     Yes                       No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_                      Print Name: Bonnie Lamond

Title: Permitting Technician                      Date: 11/14/2012                      Email: bonnie.lamond@encana.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: *Matthew Lee*                      Director of COGCC                      Date: 12/6/2012

API NUMBER                      Permit Number: \_\_\_\_\_                      Expiration Date: 12/5/2014

**API NUMBER**  
 05 045 21835 00

**CONDITIONS OF APPROVAL, IF ANY:**  
 \_\_\_\_\_

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

- (1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.
- (2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.
- (3) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE MAMM CREEK FIELD NOTICE TO OPERATORS IS REQUIRED.
- (4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)). SEE ATTACHED NOTICE.

**Applicable Policies and Notices to Operators**

Mamm Creek Field Area Notice to Operators.
Piceance Rulison Field - Notice to Operators.
NW Colorado Notification Policy.
Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field).
Notice Concerning Operating Requirements for Wildlife Protection.

**Attachment Check List**

Att Doc Num	Name
400346162	FORM 2 SUBMITTED
400346165	30 DAY NOTICE LETTER
400346166	SURFACE AGRMT/SURETY
400346167	WELL LOCATION PLAT
400346547	DIRECTIONAL DATA
400346649	DEVIATED DRILLING PLAN

Total Attach: 6 Files

**General Comments**

<b>User Group</b>	<b>Comment</b>	<b>Comment Date</b>
Permit	Surface owner is partial mineral owner in this BHL. No LGD or public comments. Final Review--passed.	12/6/2012 7:39:23 AM
Permit	Distance to nearest unit boundary is 4780'.	11/30/2012 1:33:46 PM
LGD	Passed DB	11/21/2012 12:01:58 PM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 175 FEET DEEP.	11/16/2012 3:29:14 PM
Permit	operator corrected deviated drilling plan values. This form passed completeness.	11/14/2012 11:20:23 PM
Permit	return to draft: operator to verify deviated drilling plan values match directional drilling data spreadsheet/template.	11/14/2012 1:07:39 PM

Total: 6 comment(s)

## BMP

<u>Type</u>	<u>Comment</u>
Interim Reclamation	Maintenance Revegetation Monitoring BMP maintenance & monitoring Weed Management
Construction	(Not all are used all the time) Terminal Containment, Diversions, Run-On Protection, Tracking, Benching, Terracing, ECM (Erosion Control Mulch), ECB (Erosion Control Blanket), Check Dams, Seeding, Mulching, Water Bars, Stabilized Unpaved Surfaces (Gravel), Stormwater & Snow Storage Containment, Scheduling, Phased Construction, Temporary Flumes, Culverts with inlet & outlet protection, Rip Rap, TRM (Turf Reinforcement Mats), Maintenance, Scheduling, Phased Construction, Fueling BMP's, Waste Management BMP's, Materials Handling BMP's
Pre-Construction	Wattles, Silt Fence, Vegetation Buffers, Slash, Topsoil Windrows (diversions & ROP's), Scheduling, Phased Construction
Wildlife	Minimize the number, length and footprint of oil & gas development roads Use existing routes where possible Combine utility infrastructure planning (gas, electric & water) when possible with roadway planning to avoid separate utility corridors Coordinate Employee transport when possible  Reduce visits to well-sites through remote monitoring (i.e. SCADA) and the use of multi-function contractors. Maximize use of state-of-the-art drilling technology (e.g., high efficiency rigs, coiled-tubing unit rigs, closed-loop or pitless drilling, etc.) to minimize disturbance.  Reclaim mule deer and elk habitats with native shrubs, grasses, and forbs appropriate to the ecological site disturbed.

Total: 4 comment(s)