

FORM
2

Rev
12/05

State of Colorado Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400335643

Date Received:

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

PluggingBond SuretyID

20090078

3. Name of Operator: PDC ENERGY INC

4. COGCC Operator Number: 69175

5. Address: 1775 SHERMAN STREET - STE 3000

City: DENVER State: CO Zip: 80203

6. Contact Name: Liz Lindow Phone: (303)831-3974 Fax: ()

Email: liz.lindow@pdce.com

7. Well Name: Richter Well Number: 34M-203

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 11785

WELL LOCATION INFORMATION

10. QtrQtr: SWSE Sec: 27 Twp: 7N Rng: 64W Meridian: 6

Latitude: 40.537650 Longitude: -104.531810

Footage at Surface: 237 feet FNL/FSL FSL 1410 feet FEL/FWL FEL

11. Field Name: Wattenberg Field Number: 90750

12. Ground Elevation: 4870 13. County: WELD

14. GPS Data:

Date of Measurement: 09/04/2012 PDOP Reading: 1.4 Instrument Operator's Name: Wyatt Hall

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 500 FNL 2435 FEL FEL Bottom Hole: FNL/FSL 500 FSL 2435 FEL FEL
Sec: 34 Twp: 7N Rng: 64W Sec: 34 Twp: 7N Rng: 64W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 225 ft

18. Distance to nearest property line: 237 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 267 ft

20. LEASE, SPACING AND POOLING INFORMATION

| Objective Formation(s) | Formation Code | Spacing Order Number(s) | Unit Acreage Assigned to Well | Unit Configuration (N/2, SE/4, etc.) |
|------------------------|----------------|-------------------------|-------------------------------|--------------------------------------|
| Niobrara | NBRR | | 320 | GWA |

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#: 19990086

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

NE/4, W/2SE, E/2SE in Section 34 T7N R64W

25. Distance to Nearest Mineral Lease Line: 210 ft 26. Total Acres in Lease: 318

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

| Casing Type | Size of Hole | Size of Casing | Wt/Ft | Csg/Liner Top | Setting Depth | Sacks Cmt | Cmt Btm | Cmt Top |
|-------------|--------------|----------------|-------|---------------|---------------|-----------|---------|---------|
| SURF | 12+1/4 | 9+5/8 | 36 | 0 | 875 | 830 | 875 | 0 |
| 1ST | 8+3/4 | 7 | 26 | 0 | 7,516 | 650 | 7,516 | 500 |
| 1ST LINER | 6+1/8 | 4+1/2 | 11.6 | 6311 | 11,785 | | | |

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments 7" casing string will be cemented to at least 500' below surface. Conductor casing will not be used. Operator requests an exception location per rule 318Aa and rule 318Ac: well will not be drilled in a legal drilling window or twinned with an existing well. Waviers attached. Per rule 318Ae, the Operator requests the proposed spacing unit consisting of 320 acres, W2E2 and E2W2 of Sec 34 T7N R64W. Proposed spacing unit map and 30-day certificate is attached.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Liz Lindow

Title: Regulatory Analyst Date: _____ Email: liz.lindow@pdce.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

API NUMBER

05

Permit Number: _____ Expiration Date: _____

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Data retrieval failed for the subreport 'IntPolicy_NTC' located at: W:\inetpub\Net\Reports\policy_ntc.rdl. Please check th

Attachment Check List

| Att Doc Num | Name |
|-------------|------------------------|
| 400340055 | 30 DAY NOTICE LETTER |
| 400340056 | EXCEPTION LOC WAIVERS |
| 400354655 | WELL LOCATION PLAT |
| 400354656 | DEVIATED DRILLING PLAN |
| 400354659 | EXCEPTION LOC REQUEST |
| 400354660 | DIRECTIONAL DATA |
| 400354662 | PROPOSED SPACING UNIT |

Total Attach: 7 Files

General Comments

| <u>User Group</u> | <u>Comment</u> | <u>Comment Date</u> |
|-------------------|----------------|---------------------|
| | | |

Total: 0 comment(s)

BMP

| <u>Type</u> | <u>Comment</u> |
|--------------------------------|--|
| Drilling/Completion Operations | The Colorado Oil and Gas Conservation Commission (COGCC) has established this Policy Regarding Bradenhead Monitoring During Hydraulic Fracturing Treatments ("Treatment") in the Greater Wattenberg Area ("GWA") pursuant to COGCC 207.a. ("Policy"). This Policy applies to oil and gas operations in the GWA as defined by the COGCC Rules of Practice and Procedure. PDC Energy, Inc. will comply with this policy. |

Total: 1 comment(s)