



**CEMENTER'S WELL SERVICE, INC.**  
P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

**601063**

Date	9/9/10	Well Owner	Kerr McGee	Well No.	371-347	Lease	Rock
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (MAJOR #4)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL 930				
Surface	25/8" 192-36" 13 1/2 Hole	Bottom of Surface	FL 919				
Plug		Plug Landed @	875	FL	Time On	0945	
Production		Pipe Landed @	919	FL	Plug Down	1200	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <input checked="" type="checkbox"/> Type III	1080	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1108-	1114
Disp. Rate	5 BPM	Mixing	1114-	1144
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1144-	1147
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1147-	1200
Water/Cement	6.25 Gal/SK			
Water Temp.	108°F			
Total Slurry Vol.	159.8	BBLs Cement		
Landed Plug @	400	PSI/Final Lift @ 200	PSI	
Pre-Flush W/	30	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	107.6	BBLs H <sub>2</sub> O	State	Tax
Circulate	4	BBLs Cement		Total 80612090

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		44			
1210/1217		Bulk Truck		44/44			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Cuan - Steve

Received By [Signature]

Customer or His Agent