

WELLBORE SCHEMATIC- AS OF

Machii-Ross Petroleum Co.

Well Name: Cavey 21-24

Location: NENW, Sec 12, T2N, R68W

API: 05-123-08477-00

GL Elev: 4945'

KB Elev: 4960'

Spud Date: 06/1975

Surface Casing

Date: 07/1975

8-5/8" 24#

jnts set @ 210'

Cement w/ 180 sx

Top of Cement: Surface- 0'

Top of Cement @ 4000'

Sussex

Perfs: 4423'- 4497'

Tubing detail-

Shannon

Perfs: 4881'- 4896'

Production Casing

Date: 07/1975

4-1/2" 9.5 #

jnts set @ 5029'

Cement w/350 sx

PBTD: 5000'

TVD:

TD: 5048'

TVD:

