



State
of
Colorado



Krabacher - DNR, Jay <jay.krabacher@state.co.us>

Re: Encana CBL Deferment Request (Production Casing)--MCU 26-12C (045-21606)

1 message

Krabacher - DNR, Jay <jay.krabacher@state.co.us>

To: "Reynolds, Scott D." <Scott.Reynolds@encana.com>


Cc: "Andrews, David" <David.Andrews@state.co.us>, "King, Kevin" <Kevin.King@state.co.us>

Scott:

Looks (relatively) good, no bradenhead pressure, TOC above MV and TOG, etc, Encana can defer the CBL on this well.

Regards,

Jay Krabacher



On Sun, Dec 9, 2012 at 10:34 PM, Reynolds, Scott D. <Scott.Reynolds@encana.com> wrote:

Jay,

We lost returns at the end of this cement job and the temp log put the TOC right at 200' of cement over the MV. The Bradenhead pressure has remained at zero so I am confident we got a good cement job. However, the CBL/RST will tell the story when we put together the RTC's

Encana CBL Deferment Request (Production Casing)

Well Name:	MCU 26-12C
API Number:	05-045-21606-00
Pad Name:	I27W
Casing Size	4-1/2" 11.6# S80 BTC
Casing Setting Depth	9,392 MD-RKB
Plug Bump Date:	12-02-2012
Plug Bump Time:	12:30 hrs
Top of MV:	5803' MD-RKB
Top of Gas:	7309' MD-RKB
Designed TOC:	5103' MD-RKB
Temp Log TOC:	5600' MD-RKB

Bradenhead Pressure Report

Time	Bradenhead Pressure
6 hours	0
12 hours	0
24 hours	0
48 hours	0
72 hours	0

**Comments:**

Lost Returns w/ 15 bbls remaining, attempt to stage last 15 bbls w/ no returns. Final Circ Press: 1183 psi, Bump Plug @ 2047 psi, Held Press & Bled back 1.2 bbls, Check Float Held OK. Annulus was static

Best Regards,

Scott Reynolds

Drilling Engineer – South Piceance

Encana Oil & Gas (USA) Inc

O: 720.876.5255

C: 303.895.0445

F: 720.876.6255

scott.reynolds@encana.com

Take a closer look: www.encana.com

Please note: Encana offices are closed the first and third Friday of each month

This email communication and any files transmitted with it may contain confidential and or proprietary information and is provided for the use of the intended recipient only. Any review, retransmission or dissemination of this information by anyone other than the intended recipient is prohibited. If you receive this email in error, please contact the sender and delete this communication and any copies immediately. Thank you.

<http://www.encana.com>

–
Jay Krabacher

cosas son mas como son ahora que ellas siempre fueron