

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400322077

Date Received:

10/25/2012

PluggingBond SuretyID

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refilling ☐

Sidetrack ☐

3. Name of Operator: WPX ENERGY ROCKY MOUNTAIN LLC

4. COGCC Operator Number: 96850

5. Address: 1001 17TH STREET - SUITE #1200

City: DENVER State: CO Zip: 80202

6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8268

Email: greg.j.davis@wpxenergy.com

7. Well Name: Federal Well Number: RU 332-5

8. Unit Name (if appl): Unit Number:

9. Proposed Total Measured Depth: 10071

WELL LOCATION INFORMATION

10. QtrQtr: Lot 2 Sec: 5 Twp: 7S Rng: 93W Meridian: 6

Latitude: 39.474661 Longitude: -107.798729

Footage at Surface: 254 feet FNL/FSL 2624 feet FEL/FWL
FNL FWL

11. Field Name: Rulison Field Number: 75400

12. Ground Elevation: 7602 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/10/2008 PDOP Reading: 3.4 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) submit deviated drilling plan.

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
1251 FSL 2036 FEL 1251 FSL 2036 FEL
Sec: 5 Twp: 7S Rng: 93W Sec: 5 Twp: 7S Rng: 93W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 2042 ft

18. Distance to nearest property line: 1227 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 429 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Williams Fork	WMFK	139-76		

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC41916

22. Surface Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T6S-R93W: Sec 20: SE/4; Sec 32: All; T7S-R93W: Sec 5: Lots 1, 2, S/2; Sec 6: SE/4

25. Distance to Nearest Mineral Lease Line: 1251 ft

26. Total Acres in Lease: 1362

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	18	48#	0	60	25	60	0
SURF	13+1/2	9+5/8	32.3#	0	1,113	294	1,113	0
1ST	8+3/4	4+1/2	11.6#	0	10,071	977	10,071	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Closed Loop. See WPX Master APD

34. Location ID: 383328

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Greg Davis

Title: Supervisor Permits Date: 10/25/2012 Email: greg.j.davis@wpxenergy.com

Operator must have a valid water right or permit allowing for industrial use or purchased water from a seller that has a valid water right or permit allowing for industrial use, otherwise an application for a change in type of use is required under Colorado law. Operator must also use the water in the location set forth in the water right decree or well permit, otherwise an application for a change in place of use is required under Colorado law. Section 37-92-103(5), C.R.S. (2011).

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: Matthew Lee Director of COGCC Date: 11/26/2012

API NUMBER

05 045 21772 00

Permit Number: _____ Expiration Date: 11/25/2014

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS IS REQUIRED.

(3) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE MAMM CREEK FIELD NOTICE TO OPERATORS IS REQUIRED.

(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY IS REQUIRED. (PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDERS NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010)). SEE ATTACHED NOTICE.

Applicable Policies and Notices to Operators

Mamm Creek Field Area Notice to Operators.

Piceance Rulison Field - Notice to Operators.

NW Colorado Notification Policy.

Bradenhead Pressure Reporting-Garfield County (Mamm Creek & Rulison Fields) Mesa County (Buzzard Field).

Notice Concerning Operating Requirements for Wildlife Protection.

Attachment Check List

Att Doc Num	Name
400322077	APD APPROVED
400322645	WELL LOCATION PLAT
400322646	TOPO MAP
400334880	DIRECTIONAL DATA
400335615	DEVIATED DRILLING PLAN
400339343	FED. DRILLING PERMIT
400349750	FORM 2 SUBMITTED

Total Attach: 7 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	No LGD or public comments. Final Review--passed.	11/20/2012 11:23:44 AM
Permit	Added related 2A. Corrected spacing order unit acreage & designation.	11/9/2012 10:28:20 AM
LGD	Passed DB	11/6/2012 11:27:32 AM
Engineer	THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1-MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 160 FEET DEEP.	10/31/2012 1:41:30 PM
Permit	This form passed completeness.	10/28/2012 2:30:54 PM

Total: 5 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)