

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



Document Number:

400353078

Date Received:

12/12/2012

PluggingBond SuretyID

20110198

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: CONDOR ENERGY TECHNOLOGY LLC

4. COGCC Operator Number: 10394

5. Address: 3315 HIGHWAY 50

City: SILVER SPRINGS State: NV Zip: 89429

6. Contact Name: Angie Galvan Phone: (281)716-5730 Fax: (281)815-2882

Email: Angie.Galvan@stxra.com

7. Well Name: Waves Well Number: 2H

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 11649

WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 18 Twp: 7N Rng: 59W Meridian: 6

Latitude: 40.568750 Longitude: -104.030320

Footage at Surface: 274 feet FNL/FSL 313 feet FEL/FWL FWL

11. Field Name: WILDCAT Field Number: 99999

12. Ground Elevation: 4888 13. County: WELD

14. GPS Data:

Date of Measurement: 09/02/2012 PDOP Reading: 1.8 Instrument Operator's Name: MARC WOODARD

15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 640 FSL 650 FWL 1550 FNL 680 FEL FWL  
Bottom Hole: FNL/FSL 1550 FNL 680 FEL FWL  
Sec: 18 Twp: 7N Rng: 59W Sec: 18 Twp: 7N Rng: 59W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 240 ft

18. Distance to nearest property line: 274 ft 19. Distance to nearest well permitted/completed in the same formation(BHL): 1 mi

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
NIOBRARA	NBR	535-205	640	18

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: 20110197

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

Lot 2, Lot 3, Lot 4, SE/4NW/4, E/2SW/4, SE/4, Section 18, Township 7 North, Range 59, 6th PM and W/2 Section 23 Township 7 North, Range 60 West, 6th PM Weld County, Colorado

25. Distance to Nearest Mineral Lease Line: 0 ft

26. Total Acres in Lease: 726

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	75	0	40	20	40	0
SURF	12+1/4	9+5/8	36	0	1,000	500	1,000	0
1ST	8+3/4	7	23	0	6,560	650	6,560	
1ST LINER	6+1/8	4+1/2	11.6	5440	11,649			

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments This Form 2 is being submitted with the Form 2A (Document Number 400353121)

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Angie Galvan

Title: Regulatory Analyst

Date: 12/12/2012

Email: Angie.Galvan@stxra.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

Date retrieval failed for the subreport 'IntBelief\_NTC' located at: W:\Intpub\Net\Reports\belief\_ntc.rdl. Please check th

### Attachment Check List

Att Doc Num	Name
400353078	FORM 2 SUBMITTED
400353111	WELL LOCATION PLAT
400356221	30 DAY NOTICE LETTER
400357282	DIRECTIONAL DATA
400357283	DEVIATED DRILLING PLAN

Total Attach: 5 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Construction	<p>Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-off/run-on and the release of fluids for the location. See attached Construction Layout Drawing.</p> <p>The Location will be fenced and the fenced area will include the Fresh Water Storage Pit.</p>
Drilling/Completion Operations	<p>Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.</p> <p>Fresh water for the Fresh Water Storage Pit comes from a water provider; water sources permitted for consumable industrial use.</p>

Total: 2 comment(s)