




State
of
Colorado



02121822

Krabacher - DNR, Jay <jay.krabacher@state.co.us>



Re: UPDATE--Encana CBL Deferment Request (Production Casing)--MCU 26-4B (045-21604)

1 message

Krabacher - DNR, Jay <jay.krabacher@state.co.us>

Tue, Dec 18, 2012 at 2:07 PM

To: "Reynolds, Scott D." <Scott.Reynolds@encana.com>

Cc: "King, Kevin" <Kevin.King@state.co.us>, "Andrews, David" <David.Andrews@state.co.us>

Greetings, Scott:

Encana can defer the CBL on the subject well.

Regards,

Jay Krabacher
N W Area Engineer
C O G C C

On Tue, Dec 18, 2012 at 1:43 PM, Reynolds, Scott D. <Scott.Reynolds@encana.com> wrote:


Hi Jay,

I didn't have the correct Top of MV, Top of Gas and Designed TOC in the email I just sent for this well. Please use this corrected one.

Encana CBL Deferment Request (Production Casing)

Well Name:	MCU 26-4B
API Number:	05-045-21604-00
Pad Name:	I27W
Casing Size	4-1/2" 11.6# S80 BTC
Casing Setting Depth	9,624 ft MD-RKB
Plug Bump Date:	12-15-2012
Plug Bump Time:	15:30 hrs
Top of MV:	5852' MD-RKB
Top of Gas:	7602' MD-RKB
Designed TOC:	5252' MD-RKB
Temp Log TOC:	5550' MD-RKB

Bradenhead Pressure Report



Time	Bradenhead Pressure
6 hours	0
12 hours	0
24 hours	0
48 hours	0
72 hours	0

Comments:

Lost Returns w/ 20 bbls remaining on displacement Annulus full on visual inspection. Floats held.

Temp Log TOC @ 5550' MD-RKB (MV @ 5852' MD-RKB)

Scott Reynolds

Drilling Engineer – South Piceance

Encana Oil & Gas (USA) Inc

O: 720.876.5255

C: 303.895.0445

F: 720.876.6255

scott.reynolds@encana.com

Take a closer look: www.encana.com

Please note: Encana offices are closed the first and third Friday of each month

This email communication and any files transmitted with it may contain confidential and or proprietary information and is provided for the use of the intended recipient only. Any review, retransmission or dissemination of this information by anyone other than the intended recipient is prohibited. If you receive this email in error, please contact the sender and delete this communication and any copies immediately. Thank you.

<http://www.encana.com>

-
Jay Krabacher

cosas son mas como son ahora que ellas siempre fueron