

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80203 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400355360

Date Received:

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 8960

4. Contact Name: Olga Chikaloff

2. Name of Operator: BONANZA CREEK ENERGY OPERATING COMPANY

Phone: (720) 440-6100

3. Address: 410 17TH STREET SUITE #1400

Fax: (720) 279-2331

City: DENVER State: CO Zip: 80202

5. API Number 05-123-35867-00

6. County: WELD

7. Well Name: North Platte

Well Number: J-F-24HZ

8. Location: QtrQtr: SWSW Section: 24 Township: 5N Range: 63W Meridian: 6

Footage at surface: Distance: 461 feet Direction: FSL Distance: 1317 feet Direction: FWL

As Drilled Latitude: 40.378680 As Drilled Longitude: -104.388960

GPS Data:

Data of Measurement: 10/08/2012 PDOP Reading: 1.4 GPS Instrument Operator's Name: Wyatt Hall

** If directional footage at Top of Prod. Zone Dist.: 681 feet. Direction: FSL Dist.: 979 feet. Direction: FWL

Sec: 24 Twp: 5N Rng: 63W

** If directional footage at Bottom Hole Dist.: 494 feet. Direction: FNL Dist.: 961 feet. Direction: FWL

Sec: 24 Twp: 5N Rng: 63W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 09/02/2012 13. Date TD: 09/10/2012 14. Date Casing Set or D&A: 09/12/2012

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 11270 TVD** 6514 17 Plug Back Total Depth MD 11270 TVD** 6514

18. Elevations GR 4568 KB 4583

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

Gamma Ray, CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	13+1/2	9+5/8	36	0	434	380	0	434	CALC
1ST	8+3/4	7	26	0	7,082	745	1,822	7,082	CBL
1ST LINER	6+1/8	4+1/2	11.6	7018	11,270				

STAGE/TOP OUT/REMEDIAL CEMENT

Cement work date: _____

Method used	String	Cementing tool setting/perf depth	Cement volume	Cement top	Cement bottom

Details of work:

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
SHARON SPRINGS	6,200		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	6,229		<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	6,369		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Olga Chikaloff

Title: Engineering Tech

Date: _____

Email: oChikaloff@bonanzacrk.com

Attachment Check List

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400355406	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400355403	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400355400	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400355402	DIRECTIONAL DATA	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400360543	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

General Comments**User Group****Comment****Comment Date**

--	--	--

Total: 0 comment(s)