



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

200658

Date 9-3-2012	Well Owner BONANZA CREEK	Well No. J-F-24 HZ	Lease NORTH PLATTE
County WELD	State COLORADO	Field	
Charge to BONANZA CREEK ENERGY INC	Charge Code		For Office Use Only
Address 410 17TH STREET STE #1500 (ENSTGN #129)			
City, State DENVER, COLORADO 80202			
Pump Truck No. 1201	Code	Bulk Truck No.	Code 60007271
Type of Job	Depth	Ft. 445	To
Surface 95/9 CSG. 36" 13 1/2" HOLE	Bottom of Surface	Ft. 435	To
Plug	Plug Landed @ 394	Ft.	Time On 0125
Production	Pipe Landed @ 435	Ft.	Time Off PLUG DOWN 0430

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat ✓	380	SKS		
	Poz. Mix				
	Calcium Chloride	390			
	Gel % Flo-Cele 1/4 #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
95/9	GUIDE SHOE	1			
11	CENTRALIZERS	5			
11	BAFFLE PLATE	1			
	BOX THREAD LOCK	1			
	MIXING RATE 4 BPM / DISP. RATE 5 BPM				
	SLURRY VOL 118 CU FT / SK - SLURRY WT 14.8-15				
	TOTAL SLURRY VOL 79.8 BBLs CEMENT				
	PLUG LANDED @ 825 PSI / FINAL LIFT 175 PS.				
Remarks:	Tax Reference Code	Sub Total			
PRE-FLUSH W/ 10 BBLs H2O	State CO 2.9 %	Tax			
DISPLACE W/ 30.4 BBLs H2O	Disc.	Total			
CIRCULATE 6 BBLs CEMENT					
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming
1201		Pump Truck		35	
		Bulk Truck		35/35	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JIM/JOSHA/STEVE**

Received By

Customer or His Agent