



CEMENTER'S WELL SERVICE, INC.
P.O. BOX 338220 • GREELEY, CO 80633 • (970) 353-7290 • FAX (970) 353-7712

OUR INVOICE

601022

Date 8-12-12	Well Owner Kerr McGee	Well No. 35C-2942	Lease ADORTON
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (MASON #42)			
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Fl. 950	
Surface 9 5/8" CSG-36" 13 1/2" HOLE	Bottom of Surface	Fl. 925	
Plug	Plug Landed @ 885	Fl. Time On 0130	
Production	Pipe Landed @ 925	Fl. Plug Down 0430	

Description	Qty.	Mess.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III Bulk 24	690	SKS		
Poz. Mix				
Calcium Chloride 1/2 lb 35C-2942	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge 80012070	102	Miles		
Fuel Surcharge	102	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	0324	0332	
Disp. Rate 5 BPM	Mixing	0332	0413	
Slurry Vol. 1.32 Cu.Ft./Sk	Change Valves	0413	0416	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0416	0430	
Water/Cement 6.25 Gal/SK				
Water Temp. 68°F				
Total Slurry Vol. 162.2	BBLs Cement			
Landed Plug @ 900	PSI/Final Lift @ 380	PSI		
Pre-Flush W/ 30	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 68.4	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate 6	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		34			
1214/1217		Bulk Truck		34/34			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOSHIE, JIM, ERNIE, EVAN, STEVE**

Received By

Customer or His Agent